## **Scope of Work shall include but not limited to the followings:**

- 1.DG Maintenance to be done by competent agency (OEM) once in a year and report to be submitted to Engineer In charge by six month from starting date of AMC.
- 2. All small repairing of DG Charger/UPS healthiness at MPL Colony including Guest House (MA2,MA5,MB3,MC21) to be done by Vendor and same to be reported monthly wise to Engineer In charge with proper document.
- 3. Battery Maintenance for DG/Sw.Gr./ MA2/MA5/MB3/MC21 to be done by monthly basis. Following jobs will be carried out (a) Wet Cell Battery Water Level Maintain, (b) Specific Gravity of individual cell to be maintain from 1200-1240, (c) Application of Petroleum Jelly in all battery terminals, (d) Individual cell voltage measurement. The same report to be submitted to Engineer in Charge by monthly basis.
- 4. Street light of Colony Approach road up to DVC Admin Building to be maintain by vendor.
- 5. 2nos. of Service Transformer (33000/415 V) of Colony, maintenance and DGA test by reputed organization (PGCIL/DVC) to be done once in a year
- 6. One dedicated AC technician to be provided by the vendor round the year for properly maintenance of AC in MPL Colony, Field Hostel & Guest Houses.
- 7. Any type of fault (Cable/Electrical Appliances of MPL Asset in Colony Room) to be identified and rectified by vendor with in 24hours and same report to be submitted to EI.
- 8. All lighting DB maintenance (monthly basis) to be done by vendor and report to be submitted to EI.
- 9. 415V Breaker Overhauling to be done once in a year. Detail report to be submitted after completion of job.
- 10. Earth Pit maintenance and report to be provided by vendor in 2'nd AMC Month after start the AMC period.
- 11. MPL Colony and field hostel energy meter reading to be provided by vendor by 26th of every month.
- 12. Maintenance of Fire Motors, Water Supply Motors and its accessories is under Vendor Scope. Material (Bearing, Contactor, Cable etc.) will be supplied by MPL. Motor rewinding, bearing replacement, overhauling etc. job is under vendor scope.