

18th September 2025

NOTICE INVITING TENDER (NIT)

The Tata Power Company Limited Invites Tenders through E-Tender Two-Part bidding process from interested bidders (with manufacturing / assembling facilities in India) for the following package required for its Transmission Divisions in Mumbai: -

A. Summary of the tendered package:

For the following packages contact person shall be Mr. Naman Patel (naman.patel@tatapower.com) & Mr. Vivek Mittal (vivek.mittal@tatapower.com)

Sr No.	Description	Tender Reference no.	Bid Guarantee Fee / EMD (Rs.)	Tender Fee (Rs.)
1.	EPC of 220KV 1-Core 1200 Sqmm Copper XLPE Lead Sheath cable along with associated accessories for establishment of new 220/33KV GIS substation at Worli location.	CC26NP022	35,00,000/-	2000/-

For additional technical details and Pre-Qualification criteria for the subject works please refer **Section C** below.

B. Guidelines for Participating:

Interested bidders having executed similar projects can participate by submitting the following up to **1500 hrs. Friday 26th September 2025:** -

1. Non-Refundable Tender Fee, as indicated in table above, in the form of Direct deposit in the following bank account and submit the receipt along with a covering letter clearly indicating the Tender Reference number.

Beneficiary Name – The Tata Power Co. Ltd.

Bank Name – HDFC Bank Ltd.

Branch Name – Fort Branch, Mumbai

Address – Maneckji Wadia Building, Nanik Motwani Marg, Fort, Mumbai 400023.

Branch Code – 60

Bank & Branch Code – 400240015

Account No – 00600110000763

Account type – CC

IFSC Code – HDFC0000060

2. Bidders to also submit duly signed and stamped letter indicating name of authorized person, contact number and e-mail id (mandatory) on Bidder's letterhead. It is mandatory to mention Tender Reference no. in the said letter.

Note: Once the above-mentioned documents are received, detailed RFQ shall be issued through our e-tender system (ARIBA).

It may be please noted that all future correspondence will be strictly done only with **Interested Bidders** who have done the above steps in time with Authorized Person only through Tata Power E-Tender System.

Earnest Money Deposit (EMD) of **INR 35.00 Lakhs** is not to be submitted now and is required at a later stage along with tender submission in the form of Bank Guarantee.

Section C: Pre-Qualification requirement and Bill of Quantity: (Please refer the following pages for details).

Bidders Prequalifying Requirements for 220 kV EHV Cable (Part A-Supply)

Sr No	Parameter	Tata Power Requirement	Documents to be submitted by vendor to ascertain meeting of Pre-Qualification Requirement
1	2	3	4
1	Infrastructure	<p>Bidder shall be OEM of 220 kV and above voltage class, single core XLPE cables with manufacturing facility / assembly in India, Or, Bidder shall be an EPC Contractor in a JV with OEM of 220 KV and above voltage class with manufacturing facility/assembly in India.</p>	<p>Self-undertaking to be submitted in this regard. Tata Power reserves the right to inspect the said manufacturing facility as a proof of compliance to this parameter. JV agreement copy to be submitted.</p>
2	Supply & Experience	<p>Bidder/OEM partner shall have manufactured and supplied 100 K.Ms. of 110 kV and above voltage grade XLPE Cables in last 5 years as on original bid submission date.</p> <p>Out of above 100 K.Ms. length, minimum 20 K.Ms. cable length supplied shall be of 220 kV class in last 5 years as on original bid submission date.</p> <p>The XLPE cables of 110 kV and higher voltage class supplied by the Bidder should have been in satisfactory commercial operation for a minimum of 25 K.Ms. length, for minimum period of last 2 years as on the original bid submission date. Out of the above 25 K.Ms., minimum 1.5 K.Ms. of 220 kV class cable shall be in service for last two year as on original bid submission date.</p> <p>Indian Subsidiaries / JV of global companies (Parent) registered & having plant in India can be considered provided the Parent supports the bidder to meet the PQR. In such cases, documentary evidences shall be furnished for proving the Parent - Subsidiary / JV relationship and a Backup guarantee of five years for successful operation of the cable shall be furnished by the Parent.</p> <p>In case the bidder has a previous association with any of Tata Power Group companies for similar products and services, the performance feedback of the bidder by the Tata Power Group companies shall only be considered for evaluation purpose, irrespective of performance certificates issued by any third organization.</p>	<p>Supply List / Performance Certificates from the utilities / clients</p> <p>Relevant documentary evidences & a Backup guarantee.</p>
3	Type Test	<p>The bidder/OEM partner shall have conducted PreQualification tests on the cable offered as per IEC 62067. The bidder shall submit Type test reports obtained from third party NABL/ International Accredited Lab as per IEC 62067 for 220kV or higher voltage grade XLPE cable and accessories. The type tests should have been conducted on the equipment / material of the same design.</p> <p>The type tests should have been conducted within 5 years prior to the date of bid opening. Time period for type test may be extended by another 5 years as a special case, if there is no change in design / material of construction (MOC).</p> <p>In case the type test reports furnished are not for the quoted cable but for the cable with different voltage class and/or different conductor size, then type test shall be carried out for the offered cable from NABL / International Accredited Lab without any cost implication to the owner and the Type Test reports shall be submitted before despatch of the Cable System.</p>	<p>Type Test Report.</p> <p>Undertaking that there is no change in design / material of construction (MOC) if Type Test Report older than 5 years but less than 10 years prior to date of bid opening has to be considered (if applicable)</p> <p>Undertaking that type test shall be carried out for the offered equipment / material from NABL / International Accredited Lab without any cost implication to the owner and the Type Test reports shall be submitted before despatch of the equipment / material, in case type test reports furnished are not for the quoted equipment / material but for the equipment / material with higher voltage class and/or different capacity, (if applicable)</p>

Bidder Shall Qualify Part A & Part B			
Bidders Prequalifying Requirements for 220 kV EHV Cable (Part B-EPC)			
Sr No	Parameter	Tata Power Requirement	Documents to be submitted by vendor to ascertain meeting of Pre-Qualification Requirement
1	2	3	4
1	Execution Capability	<p>1.0 Bidder should have executed minimum 3 nos of EHV cable system projects or work orders (110 kV & Above) in Tier 1 Cities (Category "X") (viz. Delhi, Mumbai, Kolkata, Chennai, Bangalore, Hyderabad, Ahmedabad & Pune) with following scope:-</p> <p>a) Supply of EHV cable system from OEM. b) Liasoning for obtaining statutory approvals required for EHV cable laying. c) Civil works for cable trench, joint bays. d) Laying, Jointing / Termination of cable system. e) Backfilling and reinstatement of cable trench and commissioning of cable system.</p> <p>2.0 Bidder should have commissioned not less than 10.00 K.Ms. in last 5 Yrs as any Single Order.</p> <p>In case the bidder has a previous association with any of Tata Power Group companies for similar products and services, the performance feedback of the bidder by the Tata Power Group companies shall only be considered for evaluation purpose, irrespective of performance certificates issued by any third organization.</p>	List of Projects executed and certificates from utilities / clients.
2	Projects in Service	Out of the 3 projects or work orders executed by the bidder, at least one project executed by the bidder shall be in service satisfactorily for minimum of three years as on date of bid submission.	Performance Certificates from the utilities / clients
3	Commercial Capability	Average Annual turnover of the bidder for last three years shall not be less than INR 150 Crores.	<p>Profit and Loss Statements, Balance Sheet, Cash Flow Statements for the Three (3) preceding financial years duly audited and approved by Authorized Audit Firm / CA.</p> <p>In case of JV, bidder to submit statement from Chartered Accountant (CA) certifying:-</p> <p>(a) Equity stake of the partners in the Joint Venture and (b) Sum of Each Partners turnover multiplied by their respective equity stake in JV for last 3 years should exceed the Tata Power requirement (c) JV to have positive Network for preceding year. Incase JV does not have positive Network then all partners to have positive Network for preceding year.</p> <p>Backup guarantee document to be submitted by JV Partners to support the JV till execution of the project till completion of execution and completion of Latent Defect Liability Period.</p>
4	Supply	Bidder or its OEM partner shall meet the qualifying requirement as mentioned in Part A .	Bidders confirmation.
5	Warranty	Bidder shall provide 5 years warranty for the supplied and installed Cable System. In case Bidder is an EPC Contractor, the warranty and gurantee on cable system shall be provided by the OEM. The OEM shall stand gurantee on the project and shall furnish authorization cum undertaking (As per format given in tender)	Bidders confirmation. Authorization cum Undertaking by OEM.
6	Other	One OEM shall submit only 01 bid (either directly or in partnetship with an EPC contrator).	

**BOQ-Design, Engineering, Manufacturing, Factory Acceptance Test, Transportation to site, Installation and Commissioning of 220 kV
Worli RSS Project with 220 kV 1Cx1200 mm² Cu Conductor XLPE lead sheath cables**

SUPPLY PART

Sr. No.	Item Description	Quantity	Spare	Total Qty.	UoM
1	Supply of 220 kV 1C x 1200 Sq.mm CU con XLPE, lead sheath cables	15120	0	15120	Mtrs.
2	Sealing End for GIS & TRF termination with Cable 220 kV 1C XLPE Copper 1200 sq mm as per specifications	18	3	21	Nos
3	Supply of cross bonded/straight joints for 220 kV 1C 1200 Sqmm Cu. XLPE Cable	30	4	34	Nos
4	Supply of cross bonded/straight joints required for LILO with existing cable of 220 kV 1C 1200 Sqmm Cu. XLPE Cable	6	0	6	Nos
5	Supply of Three Phase link box with/without SVL for cross bonding	10	2	12	Nos
6	Supply of Co-axial Cable along with Lugs and Connectors	500	0	500	Mtrs.
7	Supply of Single Phase link box for sheath bonding	18	0	18	Nos
8	Sheath Bonding Cable	400	0	400	Mtrs.
9	Supply of HDPE pipes for EHV cable (OD 250 mm & 6 mtr length)	1000	0	1000	Nos
10	Supply of Fibre optic cable (Quantity considered 3 no. 96 Core FO cable per circuit)	33600	1000	34600	Mtrs.
11	Cable Cleats	100		100	Nos
12	Galvanised Steel structure for cable Cleating arrangement	25		25	MT
13	Supply of Fiber termination Rack	2		2	Nos
14	Supply of HDPE pipes for FO cable (dia 40 mm)	34600		34600	Mtrs.
15	No. of FO joint boxes for 96F cable	46	5	51	Nos
16	No. of termination kits (96F)	14	2	16	Nos
17	Supply of cable tiles	21600		21600	Nos
18	Patch Cord for 96F Optic Fiber Cable	200		200	Nos

SERVICE PART

PART A - For EHV Cable

Sr. No.	Item Description	Quantity	Spare	Total Qty.	UoM
1	Detailed surveying of the cable route along the alignment fixed by the owner, preparation of profile drawings for cable laying, and preparation of the final cable route in 6 sets of hard and soft copies at a scale of 1:10. The drawings should indicate the positions of cable jointing chambers, earthing details, positions of cable route markers, landmarks, etc. After completing the work and energizing for permanent record use, GPS mapping of utilities should be included in the final drawings.	2400		2400	Mtrs.
2	Excavation of cable trenches as per approved drawings, with proper wooden shoring, de-watering arrangements, and sufficient clearances from all sites. Excavation in all types of soil, except hard murrum, earth rock/debris, and backfilled earth, where underground service lines are likely to be present. Shoring the trenches, demolition of PCC, brickwork, and rubble masonry encountered while making the trenches. Disposal of excavated earth within 24 hours. Laying of PCC bed erecting side tiles. Warning tape as per approved trench drawing. Backfilling with STB up to 660 mm as per trench drawing. Backfilling above RCC tiles up to road level with excavated earth as per the approved trench drawing, with compaction and obtaining NOC from the concerned authority/agency, complete (for Double circuit). Trench cross-section drawings shall be prepared by the bidder as per specifications and approved by the owner.	1600		1600	RMtr
3	Excavation for Major road crossing as per approved drawings, with proper de-watering arrangements and sufficient clearances from all sites. Excavation in all types of soil, including hard murrum, earth rock, debris, and backfilled earth, where underground service lines are likely to be present. Demolition of PCC, brickwork, or rubble masonry encountered while making the trenches, with disposal of excavated earth within 24 hours. Laying of PCC bed and HDPE pipes, and erecting side tiles as per the approved trench drawing. Backfilling with a sand-metal mix, warning tape, and reinstating the top with soling, compaction, asphalt, and PCC M20 or as per statutory requirements on top of the crossing. (For Double circuit). Trench cross-section drawings shall be prepared by the bidder as per specifications and approved by the owner.	500		500	RMtr
4	Excavation for Minor road crossing as per approved drawings, with proper de-watering arrangements and sufficient clearances from all sites. Excavation in all types of soil, including hard murrum, earth rock, debris, and backfilled earth, where underground service lines are likely to be present. Demolition of PCC, brickwork, or rubble masonry encountered while making the trenches, with disposal of excavated earth within 24 hours. Laying of PCC bed and HDPE pipes, and erecting side tiles as per the approved trench drawing. Backfilling with a sand-metal mix, warning tape, and reinstating the top with soling, compaction, asphalt, and PCC M20 or as per statutory requirements on top of the crossing. (For Double circuit). Trench cross-section drawings shall be prepared by the bidder as per specifications and approved by the owner.	500		500	RMtr
5	Services for laying of tiles 660x500x60 mm complete (including shifting, transportation and laying in trench).	21600		21600	Nos
6	Services for un-coiling & laying 220 kV, 1200 Sq.mm XLPE insulated cable as per approved drawing & specification in open trench & through HDPE pipe laid along the route, including Loading from store, transportation, unloading at site, returning cable drum to tata power warehouse, permits from concern authority, trefoil formation, phase marking complete.	15120		15120	Mtrs.
7	Services for uncoiling and laying 96-core optical fiber cable of the specified type along the cable trench through HDPE pipe, as per the approved drawing and specification, including loading from the store, transportation, unloading at the site, returning the cable drum to Tata Power warehouse, obtaining permits from the concerned authorities, labor charges, and testing.	34600		34600	Mtrs.
8	Services for OFC splicing & termination	14		14	Nos
9	Construction of FO cable hand hole	51		51	Each

10	Services for the construction of a cable jointing chamber (RCC type) along with a below-ground earth mat (including supply of material as per specification) for the joint bay of suitable dimensions, as mutually agreed, for 1 circuit (i.e., 3 cables) with link boxes and earthing as per site requirements and specifications. This includes the supply and filling of submerged material (including supply and filling of STB) [10.0 meters]. (The final number of joint bays will be decided based on site conditions.)	10	10	Nos
11	Services for installation of straight joint/cross bonding joint of 220 kV UG cable.	36	36	Nos
12	Services for installation of GIS & Outdoor termination of 220 kV UG cable	18	18	Nos
13	Services for 40 mm dia duct for 96F optical fibre cable complete	34600	34600	Mtrs.
14	Services for termination rack for 96F optic fibre cable complete	2	2	Nos
15	Services for FO Termination box	14	14	Sets
16	Services for Joint box for FO cable	46	46	Sets
17	Installation of Link Box in Termination/Joints including earthing	28	28	Nos
18	Fabrication of Structural Steel for cable cleating arrangement	25	25	MT
19	Services for Patch Cord for 96F Optic Fiber Cable	200	200	Nos
20	Trial Pits	50	50	Nos
21	Testing & Commissioning (Per Circuit)	4	4	Lot
22	Push Jack Method with 1200 mm dia MS Pipe with 8 nos of 250 mm dia HDPE pipes	50	50	Mtrs.
23	HDD for Major Road Crossing (Consider 8 nos of Pipe for mentioned length)	200	200	Mtrs.
24	Reinstatement charges inside TATA Power Worli Premises	200	200	Mtrs.