

The Tata Power Company Limited Invites Tenders through E-Tender Two-Part bidding process from interested bidders (with manufacturing / assembling facilities in India) for the following electrical package required for its Transmission Division: -

Procedure for Participating in Tender

Tender Enquiry No.	Work Description	EMD (Rs.)	Tender Participation Fee (Rs.)	Last date & time for Payment of Tender Participation Fee*
CC26ASM001	Civil Works for Installation of Solar Panels and Accessories at Trombay Receiving Station in Mumbai.	50,000 /-	2,000/-	Friday, 9 th January 2026, 15:00 Hrs.

*** Interested bidder is strongly advised not to wait by above time and purchase the tender immediately to get the link for bid submission. This will enable them to communicate/raise queries against the subject tender in time.**

Procedure for Participating in Tender. Following steps to be done before last date for purchase of tender,

1. Interested bidder to refer to the Section C: "Pre-Qualification Requirement" (PQR).
2. Eligible and Interested Bidder to submit duly signed and stamped letter on Bidder's letterhead indicating,
 - a. Tender Enquiry number.
 - b. Name of authorized person.
 - c. Contact number.
 - d. E-mail id.
 - e. Details of submission of Tender Participation Fee.
3. Non-Refundable Tender Participation Fee, as indicated in table above, to be submitted in the form of Direct deposit in the following bank account and submit the receipt along with a covering letter clearly indicating the Tender Reference number –

Beneficiary Name – The Tata Power Co. Ltd.

Bank Name – HDFC Bank Ltd.

Branch Name – Fort Branch, Mumbai

Address – Maneckji Wadia Building, Nanik Motwani Marg, Fort, Mumbai 400023.

Branch Code – 60

Bank & Branch Code – 400240015

Account No – 00600110000763

Account type – CC

IFSC Code – HDFC0000060

E-mail with necessary attachment of 1 and 2 above to be send to amol.mote@tatapower.com and with copy to vivek.mittal@tatapower.com before “Last date and time for Payment of Tender Participation Fee”.

Interested bidders to submit Tender Participation Fee and Authorization Letter before Last date and time as indicated above after which link from Tata Power E-Tender system (Ariba) will be shared for further communication and bid submission.

Please note all future correspondence regarding the tender, bid submission, bid submission date extension, Pre-bid query etc. will be strictly done only with interested bidders who have done the above steps in time with Authorized Person only through Tata Power E-Tender system (Ariba). User manual to guide the bidders to submit the bid through e-Tender system (Ariba) is also enclosed.

No e-mail or verbal correspondence will be responded. All communication will be done strictly with the bidder who have done the above steps (Payment of tender fee and submission of letter with requisite details) to participate in the Tender.

Also, it may be strictly noted that once date of “Last date and time for Payment of Tender Participation Fee” is lapsed no Bidder will be sent link from Tata Power E-Tender System (Ariba). Without this link vendor will not be able to participate in the tender. Any last moment request to participate in tender will not be acknowledged.

Any payment of Tender Participation Fee / EMD by Bidder who have not done the pre-requisite within stipulated timeline will not be refunded.

Also, all future corrigendum to the said tender, if any, will be informed on Tender section on website <https://www.tatapower.com>

Earnest Money Deposit (EMD) is not to be submitted now and is required at a later stage along with tender submission in the form of Bank Guarantee and NEFT.

Techno Commercial PQR

Techno Commercial PQR					
To be filled by Tata Power				To be filled by Bidder	
Sr No	Parameter	Tata Power Requirement	Documents to be submitted by vendor to ascertain meeting of Pre-Qualification Requirement	Bidder Submission against Tata Power PQR Requirement	Documents submitted by Bidder to ascertain meeting of Pre-Qualification Requirement
1	2	3	4	5	6
(A)	Experience	<p>a) The Bidder should have minimum 5 (Five) years of experience in Civil and interior works which includes false ceiling, carpentry electrical works (Attach related supporting documents), with the following qualifications:</p> <p>b) The bidder must have successfully executed similar works, including the supply of materials, with the following scope of work over the last five (5) years:</p> <p>i. Carpentry works ii. False Ceiling works iii. Similar works of like partition, windows, doors, sheeting works (Attach Purchase order copy, Certificate of Experience and Satisfactory Completion of work awarded from concerned Establishments / Companies along with their references)</p> <p>In case the bidder has a previous association with any of Tata Power Group companies for similar products and services, the performance feedback of the bidder by the Tata Power Group companies shall only be considered for evaluation purpose, irrespective of performance certificates issued by any third organization</p>	Bidder to submit credentials for supporting the noted criteria. Owner has the right to reject the bid in case it is observed that the Bidder does not meet the relevant experience for the subject works		
(B)	ISO Certifications	Bidder should possess ISO-9001, ISO-14001 and OHSAS-18001 / ISO-45001 Certification or they should provide an undertaking that they will obtain these certifications for their organization if the work is awarded to them within 2 months of qualification for the work.	Bidder to submit credentials for supporting the noted criteria. Owner has the right to reject the bid in case it is observed that the Bidder does not meet the relevant experience for the subject works.		
(c)	Commercial Capability	Average annual turnover of the Vendor for last three financial years shall not be less than INR 50 Lakh.	CA Audited Profit & Loss statement along with UDIN No. to be attached.		

Note -

- 1) Tata Power reserves the right to review and approve / reject the Bidder based on Document Submission.
- 2) The Prequalification Criteria published along with the tender "In Section C.1 Pre Qualification Criteria" is the total & complete pre-qualification requirement for the tender and shall prevail over any other/additional pre-qualification requirement mentioned elsewhere in the tender.
- 3) Apart from the above PQR bidder must also qualify in Safety evaluation. Details will be shared along with tender documents.

BOQ_Civil Works for Installation of Solar Panels and Accessories at Trombay Receiving Station in Mumbai			
Sr No	Item Description	Quantity	Unit
1	Removing False ceiling incl support Providing services for dismantling grid type / gypsum false ceiling including supporting arrangement, depositing saleable scrap to tata power stores & disposing remaining debris outside tata power premises at own risk.	55	M2
2	Dismantling of loose and fix furniture Providing all tools and tackles for careful dismantling of loose and fix furniture including its supports and framings at all heights along with necessary scaffolding/platform arrangement, Careful Removal of all type of panelling ,cladding on walls, columns, beams etc. all complete including stacking at the designated location as directed by site engineer, disposing of the debris at approved municipal corporation area, transportation lifting shifting etc complete as directed	1	EA
3	Careful removal electrical fixtures CISE,Careful removal electrical fixtures and cables etc. and storing at the space as directed by project engineer	1	EA
4	CAREFUL DISMANTLING OF DOORS AND WINDOWS, PROVIDING ALL TOOLS AND TACKLES FOR DISMANTLING OF DOORS AND WINDOWS INCLUDING ITS SUPPORTS AND FRAMINGS AT ALL HEIGHTS ALONG WITH NECESSARY STACKING AT THE DESIGNATED LOCATION AS DIRECTED BY SITE ENGINEER, DISPOSING OF THE DEBRIS AT APPROVED MUNICIPAL CORPORATION AREA, TRANSPORTATION LIFTING SHIFTING ETC COMPLETE AS DIRECTED.	10	M2
5	BRK&REM OLD TILES/DADO/SKIRTING,PLASTER SERVICE TYPE: BREAKING AND REMOVAL OF OLD TILE/DADO/SKIRTING, INCLUDING PLASTER, BREAKING OF ALL THE FOLLOWING WORKS INCLUDING CUTTING OF REINFORCEMENT IN RCC STRUCTURES, MAINTAINING HOUSEKEEPING, DISPOSAL OF DEBRIS WITHIN 100 M USING PNEUMATIC EQUIPMENTS ETC, AND HAVE TO RETURN ALL USABLE ITEM BACK TO TATA POWER STORES BY PREPARING RFW COMPLETE INCLUDING TRANSPORTATION AND DISPOSAL OF MATERIAL	55	M2
6	P&A 4 to 8 mm thk lime POP punning Providing and applying of 4 to 8 mm thick lime POP punning over all types of plastered surfaces of walls ceiling beams columns etc. to bring surface in plumb line and level, including making surface smooth, providing required grooves on top of skirting etc. The cost shall include all labor, materials, scaffolding, protecting adjoining surface, cleaning etc. complete.	50	M2
7	P&A White cement based putty P&A white cement based putty in 2 coats over all types of plasterd surfaces of walls ceiling beams columns etc. to bring surface in plumb line and level, incl. making surface smooth, providing required grooves on top of skirting etc. The cost shall include all labour, materilas, protecting adjoining surface, scaffolding, cleaning etc complete.Surface to be pre-wetted & made free of any loose particles and stains etc.	50	M2

BOQ_Civil Works for Installation of Solar Panels and Accessories at Trombay Receiving Station in Mumbai			
Sr No	Item Description	Quantity	Unit
8	P/F CMRCL flush door shtr,38mm Providing Services & material for 38 mm thick commercial flush board shutter with 1 mm thick laminate of Century / Greenlam / Kitply of required shade, 6 mm thick 2 year seasoned teakwood lipping, making any cutout for glass including fixing of glass with beading, 3 nos. 4 inches railway type hinges, 110 mm CP handle, CP aldrop, door stopper on each shutter, sneak hole with glass, painting of lipping by 2 coats of approved enamel paint.	10	M2
9	P/F Al powder coated fixed windows Providing Services & material for 38 mm thick commercial flush board shutter with 1 mm thick laminate of Century / Greenlam / Kitply of required shade, 6 mm thick 2 year seasoned teakwood lipping, making any cutout for glass including fixing of glass with beading, 3 nos. 4 inches railway type hinges, 110 mm CP handle, CP aldrop, door stopper on each shutter, sneak hole with glass, painting of lipping by 2 coats of approved enamel paint.	20	M2
10	P&A Acrylic Emulsion Paint P&A 2 coats of first quality Acrylic Emulsion paint of internal grade having VOC contain less than 50 gm/lit of Asian make ACE/Nerolac Suraksha/ICI Dulux Super Coat or approved equivalent of approved colour and shade on gypsum partition /brick/siporex wall incl. 1 coat of primer, preparing the surface to receive the primer, any addl. coat reqd. to achieve even shade and colour etc. complete. The cost shall incl. labour, materials, protecting adjoining surface, scaffolding, cleaning etc complete	100	M2
11	12mm thk ply panelling "12Mm Thk Ply Panelling (Witout Finish) ""P/F 12 Mm Thk Wall Panelling, P/F Of 12 Mm Thk Ply Board Wall/Column Panelling With All Required Back Supports If Required Including Necessary Consumable Like Nails ,Screw Etc Complete In All Respect As Directed By Eic Including The Cost Of Removing Of Old Ply And Disposal It Outside The Company Premises .Rate Shall Also Include The Cost Of Shifting ,Loading ,Transportation And Unloading Of Materials. """"	35	M2
12	19mm thk ply panelling "12Mm Thk Ply Panelling (Witout Finish) ""P/F 12 Mm Thk Wall Panelling, P/F Of 12 Mm Thk Ply Board Wall/Column Panelling With All Required Back Supports If Required Including Necessary Consumable Like Nails ,Screw Etc Complete In All Respect As Directed By Eic Including The Cost Of Removing Of Old Ply And Disposal It Outside The Company Premises .Rate Shall Also Include The Cost Of Shifting ,Loading ,Transportation And Unloading Of Materials. """"	15	M2
13	P/L floor tiles (600 x 600) Providing and fixing 600 x 600 of NITCO / Kajaria / Johnson approved quality and shade as per AOC palette in flooring, on an average 50 mm thick bedding of 1:3 cement mortar and filling joints with tile grout of ROFF or equivalent, cutting of tiles to required size, cleaning, curing, etc. Complete.	55	M2

BOQ_Civil Works for Installation of Solar Panels and Accessories at Trombay Receiving Station in Mumbai

Sr No	Item Description	Quantity	Unit
14	CISE,P&F Aluminium skirting 75mm Providing and fixing 75 mm, high 12mm thick recessed/flush-mounted aluminium skirting of make hafele in approved shade, embedded flush within wall groove formed during plastering. Skirting shall be fixed with screws or adhesive, with neat mitred joints or corner pieces, and sealed with matching silicone where required. Complete with surface preparation, fixing, finishing, and final cleaning, as per approved drawings and to the satisfaction of the Engineer-in-Charge. Rate includes all materials, labour, and accessories, measured per running metre (Rmt).	35	M
15	PF POWDER COATED GRILLS PF POWDER COATED GRILLS as directed by Engineer InCharge	25	M2
16	monolithic Gypsm brd FLS CLNG Providing all materials and fixing monolithic Gypsum board FALSE CEILING conforming to IS 2095, at all heights and facia including providing and fixing of framework as spelled out in Saint Gobain,armstrong or equivalent manufacturer catalogue. Bidder to provide adequate steel sections (Channels, I or T sections) and hanger supports to cater to the false ceiling loads. OWNER would check the design and adequacy and has the right to reject if found inadequate. Nothing extra shall be paid for making openings for AC grills, smoke detectors, electrical fixtures etc. The cutouts shall be provided with peremeter channel of adequate size of 0.5 mm thk. all around and shall be supported suitably. Verticle / inclined face shall be measured above 300 mm high only. For payment purpose false ceiling shall be measured in plan only.	55	M2
17	Concealed Box (4 module) "Concealed Box (4 module) Providing & fixing concealed modular PVC / GI box of Anchor make - 4 module"	20	EA
18	Concealed Box (6 module) "Concealed Box (6 module) Providing & fixing concealed modular PVC / GI box of Anchor make - 6 module"	15	EA
19	Concealed Box (8 module) "Concealed Box (8 module) Providing & fixing concealed modular PVC / GI box of Anchor make - 8 module"	8	EA
20	P/L 1.5MM SQ WIRE Providing & laying 1.5 M2m 3 pair wire of approved brand Polycab including PVC conduit where required, all tools and tackles, laying etc omplete as direced.	55	M
21	P/L 2.5MM SQ WIRE Providing & laying 2.5 M2m 3 pair wire of approved brand Polycab including PVC conduit where required, all tools and tackles, laying etc omplete as direced.	55	M

BOQ_Civil Works for Installation of Solar Panels and Accessories at Trombay Receiving Station in Mumbai			
Sr No	Item Description	Quantity	Unit
22	P/L 4MM SQ WIRE Providing & laying 4 M2m 3 pair wire of approved brand Polycab including PVC conduit where required, all tools and tackles, laying etc complete as directed.	25	M
23	Surface Mounted Panel LED Light 12W Providing, Installing, Testing and commissioning of surface mounted panel LED light of Bajaj, Wipro . including all necessary hardware, fittings etc. Job to be complete in all respect as directed by engineer-in-charge. 100mm dia Circular Recessed- 12 watts LED lights	6	EA
24	P/F spot light 15w Supply and fixing of Spot light of bajaj/philips/wipro make including driver circuit and all associated accessories job to be completed in all respect as directed by engineer-in-charge.	20	EA
25	P&F LED Profile Light "Providing & Fixing LED Profile Lights 25mm / 35mm thick to be fixed in False Ceiling of approved make. Colour of the body & light to be confirmed by the Architect."	15	M
26	35mm thk profile light,double strip 35Mm Thk Profile Light With Double Strip Light Brands Wipro Havells	15	M
27	P/F LED Strip Light Supply and fixing of LED strip light of bajaj or equivalent make including driver circuit and all associated accessories job to be completed in all respect as directed by engineer-in-charge. Base price Rs. 300/M	40	M
28	P/L CAT 6 Cable - D Link Providing & Laying D Link CAT 6 Cable	10	M
29	P/L Aluminium Raceway "P/L Aluminium Raceway Providing & laying Aluminium raceway of 2.5 inch X 1.5 Inch, laid to line & level with cover	7	M
30	CISE,S & I of floor junction boxes with CISE,S & I of floor junction boxes with top cover for above raceways of size 300mm x 300mm x 50mm x 2mm thick , fabricated out of M.S. sheets fully powder coated with removable screwed cover plates on all four sides for blocking the entry, including all tools and tackles etc complete as directed.	10	NO
31	CISE,P/F electrically operated roller b Supplying and fixing in position electrically operated roller blinds of approved shade and pattern of Vista/Mac, Platina . make, including all necessary standard fittings, brass hinges complete with all necessary system, hardware like handles, locks to complete the job in all respect as per manufacturer specifications and satisfaction of engineer-in-charge. The fabric shall be fire retardant	20	M2

BOQ_Civil Works for Installation of Solar Panels and Accessories at Trombay Receiving Station in Mumbai			
Sr No	Item Description	Quantity	Unit
32	Spot light - 10 watt "Spot light - 10 watt Providing & fixing circular led spot light of Phillips / Panasonic / Wipro make 10 watt light, rate shall be inclusive of removal of existing fixture, making cutout for installation and finishing the surface. Base rate Rs 1800/- per piece"	10	EA
33	P&F Decorative Hanging Light CISE, Decorative hanging light - Supply and fixing in position as approved by owner. Base rate : Rs. 5000 /-	4	EA
34	P/F TV Point with wiring SERVICE TYPE: Providing TV points with all necessary wiring , casing and capping, race ways, ,ELCB (30 mA) ,MCB of GE Power, or ABB, L&T, Siemens,Schneider or equivalent make etc. including all required accessories needed to complete entire electrical system in the dormitory building as per approved design and drawings and as directed by OWNER.	1	NO
35	P&F Telephone Port "Telephone port Providing and fixing of plug - in type telephone socket outlet (RJ-11) with G.I.outlet box and cover plate complete as required. Single plug in type	1	EA
36	P/I ALCATEL LUCENT LANDLINE TELEPHONE PROVIDING SUPPLYING INSTALLING TESTING AND COMMISSIONING OF ALCATEL LUCENT LANDLINE TELEPHONE INSTRUMENT ALONG WITH CONNECTION CORD MODEL NUMBER ALE 20H	1	EA
37	CISE,P/F PA System along with Amplifier CISE,Supply installation Testing & commissioning of PA System along with Amplifier 3 nos microphone 5 nos of wall speaker cables jack connector conduit/casing of wiring and accessories required of approved make and model as per engineer-in-charge. The cost shall include the hardware and accessories required in installation and commissioning of system in all respect to complete the job.	1	EA
38	P&F Charcoal sheet Paneling "Charcoal sheet Paneling Providing all materials and installing charcoal sheet as wall panelling, including providing and installing base frame in metal sections of appropriate thickness with ply backing if required. Sealing gaps between sheets with colour and material to give monolithic look. Base rate for charcoal louvers Rs. 750/ M2.	22	M2
39	P&F Acoustic Paneling "Acoustic Paneling on Walls & Ceiling PROVIDING AND FIXING NONWOVEN POLYSTER FIBER WALL PANELS covered in fabric of approved texture & different pattern with 9mm ply backing on ceiling or wall with required supporting system inclusive of manpower, material, tools required, transportation, scaffolding,etc. Base rate of fabric is 400 Rs/mt PLYWOOD MAKE CENTURY, GREENPLY	30	M2

BOQ_Civil Works for Installation of Solar Panels and Accessories at Trombay Receiving Station in Mumbai			
Sr No	Item Description	Quantity	Unit
40	P/S chairs Supply & Placing in position cushioned revolving chair finish-velvet or leather"	30	EA
41	P/F OF BACKPAINTED GLASS PROVIDING ALL MATERIALS AND INSTALLING BACKPAINTED GLASS, TOUGHENED, AS WALL PANELLING,PASTED ON 19MM THICK PLY, INCLUDING PROVIDING AND INSTALLING BASE FRAME IN METAL SECTIONS OF APPROPRIATE THICKNESS IF NEEDED. SEALING GAPS BETWEEN SHEETS WITH COLOUR AND MATERIAL TO GIVE MONOLITHIC LOOK. PROVIDING AND FIXING BACKPAINTED GLASSBOARD OF 6MM TOUGHENED GLASS IN ANY APPROVED COLOR FOR WRITING PURPOSE WITH BACKING OF MARINE PLY OF THICKNESS UPTO 9MM WITH NECESSARY FRAMING AND FINSHED	4	M2
42	P/F LETTERS HT. UPTO 230 MM & THK. 10 MM "PROVIDING & FIXING 3D ACRYLIC LETTERS FOR NAMING OF SIZES AS MENTIONED BELOW ON WALL WITH APPROVED DESIGN AND COLOUR INCLUDING ALL TOOLS AND TACKLES FOR FIXING ETC COMPLETE AS DIRECTED. HEIGHT UPTO 230MM AND THICKNESS 10 MM"	40	EA
43	P/S/F Photo frames 450 x 750 mm "Photo frames Providing, supplying & placing in position photo frames with printing and mounting of approved images or painting in frame of approx thickness 15-25mm in approved color by architect so as to complete the job. Size 450 x 750 mm	5	EA
44	CISE,S/P in position natural potted plan CISE,Supply and placing in position natural potted plant along with plant. The plants shall be air purifying plants. Vendor to submit catalogue of various manufacturers for sample approval and submit the physical sample of the models requested by Architect for final approval - 9inch dia	5	EA
45	CISE,P/F signage of size 6 inch X 6 CISE,Providing & fixing name plate and signage of size 6 inch X 6 inch made of SS in matt finish with required signage marked on it	4	NO
46	CISE,P/F of metal T/C patti 12mm to 20mm Providing and fixing metal T/C patti 12mm to 20mm as direct by site in charge.Vendor to submit catalogue of various manufacturers for sample approval and submit the physical sample of the models requested by Architect for final approval.	30	M
47	P/F teakwood decorative patti 15 mm thk	35	M
48	P/F teakwood decorative patti 25 mm thk	35	M

BOQ_Civil Works for Installation of Solar Panels and Accessories at Trombay Receiving Station in Mumbai			
Sr No	Item Description	Quantity	Unit
49	P/F PLY PANELING FINISHED WITH LAMINATE "P/F OF PLY PANELING FINISHED WITH LAMINATE PANELLING WORKS ON WALLS, PROVIDING AND FIXING PANELLING OF APPROVED MATERIAL ON WALLS INCLUDING PREPARATION OF BASE FRAME NECESSARY SUPPORTS AND HARDWARE, POLISHING PAINTING ETC. COMPLETE. BASE RATE OF PANELLING MATERIAL: 2500 RS/SQM PROVIDING AND FIXING WALL PANELLING IN MARINE PLY OF THICKNESS UPTO 6MM WITH NECESSARY FRAMING AND FINSHED WITH DECORATIVE LAMINATE, WITH NECESSARY SITE SPECIFIC MODIFICATIONS ETC. BASE RATE OF LAMINATE IS 550 RS/ SQMTS "	70	M2
50	P/S/F Conference table 4500 X 1350 "P/S/F Conference table (SIZE : 4500 X 1350) Carpentry work for making conference table in termite resistant commercial plywood in the approved layout finished with decorative colour laminate finish. Including the under structure made in aluminum powdercoated finish. The cost shall include all required hardware and accessories such as hinges, handles, lock and any other required to complete the job in all respect. Provision for electrical box to be done as per design. Plywood make century, greenply or equivalent. Laminate base rate Rs 550/-per sqm"	1	EA
51	P&F Perforated SS Dustbin "Dustbins Providing, supplying & placing in position perforated SS dustbins of 12 inch dia as per approved architectural palette"	3	EA
52	S/f DECAL STICKERS HEIGHT UPTO 6". "DECAL STICKERS - SUPPLYING AND FIXING IN POSITION DECAL STICKERS OF VARIOUS SIZES AS PER THE APPROVED SAMPLE. VENDOR TO SUBMIT ACTUAL SAMPLE OF DIFFERENT TYPES OF FOOD ITEMS AND FOOD QUOTES AND SYMBOLS DECAL STICKERS FOR APPROVAL. IF REQUIRED ARCHITECT SHALL SUBMIT THE REFERENCE IMAGE FOR EASY OF CONTRACTOR TO SUBMIT THE CATALOGUE HEIGHT UPTO 6"". "	1	EA
53	CISE,P/F decor accessories CISE,Supply and placing in position decor accessories such as Wall painting wall art & wall hangings etc. . Vendor to submit catalogue of various manufacturers for sample approval and submit the physical sample of the models requested by Architect for final approval.	1	EA
54	Making grooves Making grooves 20 to 50 mm wide in POP punning of C shape including finishing of grooves by paper polishing , making edges straight,etc.	30	M

BOQ_Civil Works for Installation of Solar Panels and Accessories at Trombay Receiving Station in Mumbai			
Sr No	Item Description	Quantity	Unit
55	CISE,P/F & I display cabinet using 19mm "Providing, fabricating, and installing display cabinet using 19mm BWP plywood, finished with 1mm laminate of approved shade. Shutters shall be made of 6mm toughened clear glass, fixed with approved soft-close hinges and handles. Cabinet shall include internal shelving as per design and integrated 3W–5W COB LED lights (Philips/Wipro/Havells or equivalent) for illumination, including wiring and drivers. All materials and workmanship shall conform to relevant IS standards. Vendor shall submit shop drawings and material samples for approval prior to execution. Installation shall be completed in all respects as per design and to the satisfaction of the Architect/Engineer-in-Charge."	20	M2
56	P&F Fluted MDF Panelling/ cladding Fluted/Louvered MDF Panelling/ cladding with 9/12 mm ply backing in various shapes and texture as approved. Vendor to submit catalogue of various manufacturers for sample approval and submit the physical sample of the models requested by Architect for final approval. The cost shall include all required hardware, accessories and any other required to complete the job in all respect.	20	M2
57	PP&F TATA Ppower logo Providing all tools,tackles ,materials for making & fixing of TATA Power logo with acrylic letter approved size 4" as direted by EIC	1	EA
58	P&F Acoustic Paneling "Acoustic Paneling on Walls & Ceiling PROVIDING AND FIXING NONWOVEN POLYSTER FIBER WALL PANELS covered in fabric of approved texture & different pattern with 9mm ply backing on ceiling or wall with required supporting system inclusive of manpower, material, tools required, transportation, scaffolding,etc. Base rate of fabric is 400 Rs/mt PLYWOOD MAKE CENTURY, GREENPLY	25	M2
59	CISE,P/F electrically operated roller b Supplying and fixing in position electrically operated roller blinds of approved shade and pattern of Vista/Mac, Platina . make, including all necessary standard fittings, brass hinges complete with all necessary system, hardware like handles, locks to complete the job in all respect as per manufacturer specifications and satisfaction of engineer-in-charge. The fabric shall be fire retardant	35	M2
60	P/C Carpentry work storage cabinate Carpentry work in termite resistant commercial plywood for making storage cabinets of 450mm - 600mm depth in the approved layout finished with 1 mm thk color laminate and internal to be finished in white laminate. The cost shall include all required hardware and accessories such as hinges, handles, lock and any other required to complete the job in all respect. Plywood make century, greenply or equivalent. Laminate base rate Rs 550/-per sqm	40	M2

BOQ_Civil Works for Installation of Solar Panels and Accessories at Trombay Receiving Station in Mumbai			
Sr No	Item Description	Quantity	Unit
61	P&I Charcoal louvers/ Fluted panel Providing all materials and installing Charcoal louvers / Fluted panel as wall panelling, including providing and installing base frame in metal sections with marine ply backing of appropriate thickness. Sealing gaps between sheets with colour and material to give monolithic look.	50	M2
62	CISE,P/F photo frames of 16" x 20" CISE, Vendor to submit catalogue of various manufacturers for sample approval and submit the physical sample of the models requested by Architect for final approval.	20	No
63	CISE,PF Ledge seating CISE, constructed from 19mm thick plywood (Make: Century Ply Kitply Greenply Mayur Ply Asis Ply Archid Ply) with a sturdy wooden frame supported on partition wall or floor as per approved design. The backrest shall be framed using 19mm thick plywood (same make as above) supported on a wooden framework fixed securely to the partition wall or floor. The backrest shall be finished in high-quality laminate (Make: Century Ply Kitply Greenply Mayur Ply Asis Ply Archid Ply).Height of backrest-900MM from FFL. The front panel of the seating unit shall be finished in glass acrylic laminate (Make: Greenlam Merino Euro Pratik) as per the design intent. The seating surface shall be finished with high-quality laminate (Make: Greenlam Merino Euro Pratik) and the seat top shall include 100mm thick high-density foam cushion upholstered in leatherette finish (shade and texture as approved by the architect). All carpentry work joinery finishes and fittings shall be completed in all respects with neat workmanship. The vendor shall provide material samples and catalogues for finish and upholstery approval prior to execution."	15	M

Note: Above Quantities are tentative. Tata Power reserves the right to curtailed / enhance the quantities before the placement of Purchase Order.