NOTICE INVITING TENDER - CC26SVP047

The Tata Power Company Limited Invites Tenders (Two-Part Bidding Process), from interested and eligible Vendors for the following Works required for its Transmission Receiving Stations.

A. Summary of the tendered packages:

Sr. No.	Description	Tender Reference no.	Bid Guarantee Fee / EMD (Rs.)	Tender Fee (Rs.)
1.	Refurbishment of project site office for Dharavi-Mahalaxmi cable project.	CC26SVP047	50,000 /-	2,000 /-

Interested bidder is strongly advised not to wait by above time and purchase the tender immediately to get the link for bid submission. This will enable them to communicate/raise queries against the subject tender in time.

For additional technical details and Pre-qualification criteria for the subject works please refer section C below.

B. Guidelines for Participating:

Interested and eligible vendors can participate by submitting the following up to 1500 hours on **Friday – 13th March 2026.**

1. Payment of non-refundable Tender Fee, as indicated in table above to be paid by direct deposit in following bank account

   Beneficiary Name – The Tata Power Co. Ltd.

   Bank Name – HDFC Bank Ltd.

   Branch Name – Fort Branch, Mumbai

   Address – Maneckji Wadia Building, Nanik Motwani Marg, Fort, Mumbai 400023.

   Branch Code – 60

   Bank & Branch Code – 400240015

   Account No – 00600110000763

   Account type – CC

   IFSC Code – HDFC0000060

2. Submission of duly signed and stamped Authorization Letter indicating name of authorized person, contact number and e-mail id (mandatory) on Vendor's letterhead. The letter shall also mandatorily include payment details of Tender fee and Tender Reference no **CC26SVP047.**

   Authorization Letter along with proof of submission of tender fee should be e-mail to **Ms. Sujata Vishnu Patil** (sujatavishnu.patil@tatapower.com) and copy to **Mr. Vivek Mittal** (vivek.mittal@tatapower.com)

   Note: - Once the above-mentioned documents are received, detailed RFP shall be issued through our e-tender system.

3. It is clarified that Bid Guarantee/EMD as mentioned in section "A" above, is not required to be submitted at this stage, and it will be required to be submitted in the form of Bank guarantee at the time of Bid Submission.

C. <u>Addition technical details</u>:

A2. Prequalification Criteria (Technical & Commercial:

Sr No	Parameter	Tata Power Requirement	Documents to be submitted by vendor to ascertain meeting of Pre-Qualification Requirement
1	**2**	**3**	**4**
1	**Work experience**	Bidder should have minimum 03 years' experience of Renovation work like tiling, false ceiling work, partition work. Bidder must have experience of successfully completing a minimum of following civil works during the past 3 years as on the date of bid opening. • Tiling- 300 sqm • False ceiling- 300 sqm • Partitions work – 200 sqm • Carpentry work • Electrical work In case the bidder has a previous association with any of Tata Power Group companies for similar products and services, the performance feedback of the bidder by the Tata Power Group companies shall only be considered for evaluation purpose, irrespective of performance certificates issued by any third organization.	Work completion certificate / PO. Bidder to submit credentials for supporting the noted criteria. Owner has the right to reject the bid in case it is observed that the Bidder does not meet the relevant experience for the subject works
3	**Commercial Capability**	Average Annual Turnover of the bidder for last three financial years shall not be less than INR 50 Lakh.	Audited Profit & Loss statement along with UDIN No. to be attached.

Note: Above Pre-qualification details need not be submitted at this stage. These shall be required to be submitted along with bid submission. At this stage, Interested Vendors who fulfill above criteria need to participate in tender by paying tender fee and submitting authorization letter as detailed in section "B" above.

D. <u>Estimated Quantity: (BOQ)</u>

Present tender consists of two lots as below:

LOT 1: Refurbishment of Project site office for Dharavi Mahalaxmi cable project.

LOT 2: Refurbishment of Project site office for Dharavi Mahalaxmi cable project.

Interested bidders may participate of one of both the LOTs. Please note that Techno-Commercial evaluation for both the lots shall be done separately.

BOQ - Lot 1 - Refurbishment of Project site office for Dharavi Mahalaxmi cable project.

Sr. No.	Item Description	Unit	Quantity
1	**Demolishing Brick masonary** Demolishing Brick masonary of variable thickness with plaster and disposing off the debris to the approved dumping ground of MCGM etc complete as per specifications and as directed by the Engineer..	cum	5.00
2	**Demolishing Cement Plaster** Providing all necessary tools tackels services etc. for removing plaster of all thickness as directed by the Site-Engineer and disposing of the debris to the approved dumping ground of MCGM etc. complete as per specifications and as directed by the Engineer..	sqm	30.00
3	**Dismantling of false ceiling** Dismantling and listing of all type of ceiling (monolythic, grid type etc) at all levels and locations and including stacking and listing of serviceable materials to any distance at scrap yard with in compound and disposal of unserviceable material to out side of building to the designated place within all leads or disposal of debris to designated place by local municipal corporation as per direction of Engineer-in-charge, rate shall be inclusive of man, material, tools such as ladder, hacksaw etc steel scaffolding, disposal of debris to designated place by local municipal corporation.	sqm	200.00
4	**Careful removal of fix furniture** Providing all tools and tackles for careful uninstallation of fix furniture including its supports and framings at all heights along with necessary scaffolding/platform arrangement, stacking at the designated location as directed by site engineer, disposing of the debrise at approved municipal corporation area, transportation lifting shifting etc complete as directed. Reinstallation of the fix furniture at designated position including provision and supply of all necessary tools and hardware required. as per the final design scheme	LS	1.00

5	**Removal of loose furniture** Providing all tools and tackles for careful uninstallation of loose furniture including its supports and framings at all heights along with necessary scaffolding/platform arrangement, stacking at the designated location as directed by site engineer, disposing of the debrise at approved municipal corporation area, transportation lifting shifting etc complete as directed.	LS	1.00
6	Providing all tools and tackles for **dismantling of existing wall panelling** including its supports and framings at all heights along with necessary scaffolding/platform arrangement, disposing of the debrise at approved municipal corporation area, transportation lifting shifting etc complete as directed. Carefully storing reusable material at designated location within project premises,as per direction of site engineer.	sqm	20.00
7	**Careful Dismantling and listing of electrical** fixtures such as lights, fan, Television, desktops, switch boards, sockets and hardware, AC or any other electrical equipment etc. and casing caping including wiring all complete including stacking of serviceable materials to any distance at scrap yard with in compound and disposal of unserviceable material disposing of the debrise at approved municipal corporation area, transportation lifting shifting etc complete as directed by Engineer-in-charge.	LS	1.00
8	**Careful Dismantling of doors and windows** Providing all tools and tackles for dismantling of door and windows including its supports and framings at all heights along with necessary scaffolding/platform arrangement, stacking at the designated location as directed by site engineer, disposing of the debrise at approved municipal corporation area, transportation lifting shifting etc complete as directed by Engineer in charge	sqm	30.00
9	Breaking and removal of **old tile/dado/skirting**, including plaster, all lead, lift & scaffolding, maintaining housekeeping, disposal of debris within premises etc, and have to return all usable item back to tata power stores by preparing rfw complete including transportation and disposal of material	sqm	210.00
10	Dismantling aluminum/gypsum partition ,door ,window, fixed glazing and false ceiling including disposal of unserviceable material and stacking serviceable material within plant premises as directed by EIC.	sqm	45.00

11	Providing and applying of **4 to 8 mm thick lime POP punning** over all types of plastered surfaces of walls ceiling beams columns etc. to bring surface in plumb line and level, including making surface smooth, providing required grooves on top of skirting etc. The cost shall include all labor, materials, scaffolding, protecting adjoining surface, cleaning etc. complete.	Sqm	90.00
12	P&A white cement based putty in 2 coats over all types of plasterd surfaces of walls ceiling beams columns etc. to bring surface in plumb line and level, incl. making surface smooth, providing required grooves on top of skirting etc. The cost shall include all labour, materilas, protecting adjoining surface, scaffolding, cleaning etc complete.Surface to be pre-wetted & made free of any loose particles and stains etc.	Sqm	90.00
13	**Acrylic Emulsion paint of internal grade:** Providing and applying one coat of sealant along with anti fungus treatment followed by one coat of cement primer filling up the crevices & holes including making full palti of painters putty and making the surfaces smooth and even with best quality painters putty and, applying primer on prepared surface and finishing with two coats of approved quality paint at all heights with Acrylic Emulsion paint (Internal quality) of first quality having VOC contain less tha 50 gm/lit of Asian make ACE / Nerolac Suraksha / ICI Dulux Super or of approved manufacturere, in approved shades.#Item includes providing & erecting steel scaffolding preparing the surface by scraping, sand papering, cleaning, solvent cleaning wherever required to remove oil/grease & painting all the internal, external walls, concrete surfaces, masonry surfaces with plaster or pointing, ceilings, chajjahs, fins, pardis, steel surfaces, wooden surfaces etc will be painted as per existing shade or as per the shade approved approved by owner at all heights.	sqm	300.00
14	Providing and fixing 12 mm thick Vitrified tiles of Nitco or equivalant / Kajaria / Johnson approved quality and shade in flooring on a 20 mm thick bedding of 1:3 cement mortar and jointed with white/ coloured cement slurry, cutting of tiles to required size, cleaning, curing, etc. complete. Size 600x600	sqm	100.00
15	"Providing and fixing 12 mm thick Vitrified tiles of Nitco or equivalant / Kajaria / Johnson approved quality and shade in flooring on a 20 mm thick bedding of 1:3 cement mortar and jointed with white/ coloured cement slurry, cutting of tiles to required size, cleaning, curing, etc. complete. Size 1200x600	sqm	110.00

16	CISE,Providing and fixing 75mm high skirting of Vitrified tiles of Nitco /RAK or Kajaria make of approved quality shade and size as mentioned below on a 20 mm thick bedding of 1:3 cement mortar and jointed with white/ coloured cement slurry cutting of tiles to required size cleaning curing etc. complete.	M2	60.00
17	Providing and fixing at least 15 mm thick machine cut machine polished pitch black granite stone of any sizes for counter / cooking/platform with necessary cement mortar bedding and floating with matching colour cement, curing, polishing, cleaning etc or cutting grooves in walls, full bull nose or double bull nose molding & polishing of edges & redoing in cm (1:3) complete.	sqm	5.00
18	Providing and fixing Aluminium powder coated **8 Slott AC grill of 300MM** width at required location and required height as per design, drawing and site condition including all materials, tools & tackles, scaffolding, etc. complete as per instructions of Engineer-in-charge.	EA	15.00
19	Providing and fixing in position minimum 10-12 mm Thk. clear toughened glass partition of st. gobain, modiguard. Glass to be fixed with framing sections anodised black coated Aluminum Partition Frame in wall and floor including all required accessories and hardware etc. required to complete the job in all respect. All exposed edges of the glass shall be machine polished. All glass-to-glass joints to be sealed with pre-approved sillicon sealants.	SQM	15.00
20	PROVIDING AND FIXING BEST QUALITY 38MM THICK SINGLE/DOUBLE LEAF FLUSH DOOR FRONT / EXTERNAL DOOR SHUTTER FINISHED WITH APPROVED 1.5MM THK. COLOUR LAMINATE OF APPROVED MAKE FROM BOTH SIDE, WITH 125MM X 75MM TEAK WOOD FRAME WITH PROVISION OF 10 MM THICK TEAK WOOD BEADING AROUND THE SHUTTER ETC. COMPLETE INCLUDING AND ALL OTHER NECESSARY FIXTURES AND FITTINGS HEAVY DUTY RAILWAY TYPE HINGES ETC . WITH /WITHOUT VISION GLASS PANEL.	SQM	5.00
21	Providing and fixing **both sided gypsum Partition** walls using Gyprock soundblock board of required thickness of saint Gobain or equivalent as per approved drawings including scaffolding/access, making cut-out of required sizes and supporting framework for door opening as specified in approved drawings and manufacturer specification using metal stud frame sections ,ceiling sections , connecting clip, drywall screws, anchor bolts, backing strips, includes filling and finishing with Jointing compound, Joint Paper tape and two coats of Drywall Top Coat as specified in specification , etc.all complete as per the the approved drawings and Manufacturer specifications and engineering drawings.	SQM	12.00

22	Providing & applying Garvare make **sun control film** of required shade, Garware make high heat rejection film HHR 25	Sqm	10.00
23	P/F of single / double leaf framed glass door with minimum 12mm thk. glass toughened by horizontal process of St. gobain, modi guard make.the door shall be with frame in MS/Ply/Wood & incl. all necessary hardware such as using patch fittings,double action hydraulic heavy duty floor spring IS:6315, door handle on both sides incl.cost of cutting floors as required.All hardwares shall be of Godrej, Dorma.Note: Hardware required:H Type SS satin finish push pull door handle for door.	SQM	11.00
24	Providing all materials and fixing **monolithic Gypsum board FALSE CEILING** conforming to IS 2095, at all heights and facia including providing and fixing of framework as spelled out in Saint Gobain,armstrong . manufacturer catalogue. Bidder to provide adequate steel sections (Channels, I or T sections) and hanger supports to cater to the false ceiling loads. OWNER would check the design and adequacy and has the right to reject if found inadequate. Nothing extra shall be paid for making openings for AC grills, smoke detectors, electrical fixtures etc. The cutouts shall be provided with perimeter channel of adequate size of 0.5 mm thk. all around and shall be supported suitably. Vertical / inclined face shall be measured above 300 mm high only. For payment purpose false ceiling shall be measured in plan only.	Sqm	210.00
25	Making grooves 20 to 50 mm wide in POP punning of C shape including finishing of grooves by paper polishing , making edges straight,et c.	RMT	25.00
26	P/F of Switch boards 4 module "Providing and fixing Switch boards of Anchor (Roma series), Havells (Oro series), MK Switches (Ivory), Legrand (Myrius White) or equivalent make required to cater all the light points, luminary, AC, TV sceens and all other electrical fixture. including all other accessories required to complete the job in all respect and as directed by engineer-in-charge. 4 module"	EA	6.00
27	**P/F of Switch boards 6 module** "Providing and fixing Switch boards of Anchor (Roma series), Havells (Oro series), MK Switches (Ivory), Legrand (Myrius White) or equivalent make required to cater all the light points, luminary, AC, TV sceens and all other electrical fixture. including all other accessories required to complete the job in all respect and as directed by engineer-in-charge. 6module"	EA	20.00

28	**P/F of Switch boards 8 module** "Providing and fixing Switch boards of Anchor (Roma series), Havells (Oro series), MK Switches (Ivory), Legrand (Myrius White) or equivalent make required to cater all the light points, luminary, AC, TV sceens and all other electrical fixture. including all other accessories required to complete the job in all respect and as directed by engineer-in-charge. 8 module"	EA	20.00
29	**P/F of Switch boards 12 module** "Providing and fixing Switch boards of Anchor (Roma series), Havells (Oro series), MK Switches (Ivory), Legrand (Myrius White) or equivalent make required to cater all the light points, luminary, AC, TV sceens and all other electrical fixture. including all other accessories required to complete the job in all respect and as directed by engineer-in-charge. 12 module"	EA	2.00
30	**P/F of Switch boards 16 module** "Providing and fixing Switch boards of Anchor (Roma series), Havells (Oro series), MK Switches (Ivory), Legrand (Myrius White) or equivalent make required to cater all the light points, luminary, AC, TV sceens and all other electrical fixture. including all other accessories required to complete the job in all respect and as directed by engineer-in-charge. 16 module"	EA	1.00
31	**1.5 mm wiring** "1.5 mm wiring Installation of mains wiring including supply of 1X1CX2.5 mM2 + 2X1CX1.5 mM2 copper wire for socket outlet point in 25 mm medium gauge rigid PVC conduits as concealed manner, modular switch board, earthing with copper wire laid inside the conduit etc. Supply and laying of 25 mm PVC conduit is not included in this item."	RMT	500.00
32	**2.5 mm wiring** "2.5 mm wiring Installation of mains wiring including supply of 2X1CX2.5 mM2 + 1X1CX1.5 mM2 copper wire in 25 mm medium gauge rigid PVC conduits as concealed manner, modular switch board, earthing with copper wire laid inside the conduit etc. Supply and laying of 25 mm PVC conduit is not included in this item. Mains wiring is defined as necessary wiring from distribution board to respective switch boards and modular 5/15A switch socket units."	RMT	1,000.00
33	Providing & laying **4 sqmm 3 pair wire** of approved brand Polycab including PVC conduit where required, all tools and tackles, laying etc omplete as direced.	RMT	100.00
34	**6 Amp switch** "6 Amp switch Providing & fixing 6A single pole one way switch of Anchor make Roma series, rate shall be inclusive of man, material, transportation & installation along with connection to wiring"	EA	50.00

35	**6 Amp socket** "6 Amp socket Providing & fixing 6 A Anchor make Roma series sockets, rate shall be inclusive of man, material, transportation & installation along with connection to wiring"	EA	20.00
36	**16 Amp switch** "16 Amp switch Providing & fixing 16 amp switch of Anchor make Roma series or Legrand make Myrius white series, rate shall be inclusive of man, material, transportation & installation along with connection to wiring"	EA	10.00
37	**16 Amp socket** "16 Amp socket Providing & fixing 16 A Anchor make Roma series sockets, rate shall be inclusive of man, material, transportation & installation along with connection to wiring"	5.00	5.00
38	**P/F 16 Amp RCCB** Prov & installating 16 Amp RCCB of Anchor / L & T / Havells / equivalent make including connection with wire	EA	5.00
39	**S & I of RCCB 2P 20A 30mA** Supply, Installation, Testing and commissioning of RCCB 2P 20A 30mA	EA	2.00
40	**Concealed Box (2 module)** , Providing & fixing concealed modular PVC / GI box of Anchor make - 2 module	EA	5.00
41	**Concealed Box (3 module)** Providing & fixing concealed modular PVC / GI box of Anchor make - 3 module	EA	5.00
42	**Concealed Box (4 module)** Providing & fixing concealed modular PVC / GI box of Anchor make - 4 module	EA	6.00
43	**Concealed Box (6 module)** Providing & fixing concealed modular PVC / GI box of Anchor make - 6 module	EA	20.00
44	**Concealed Box (8 module)** Providing & fixing concealed modular PVC / GI box of Anchor make - 8 module	EA	4.00
45	**Concealed box (9 module)** Providing & fixing concealed modular PVC / GI box of Anchor make - 9 module	EA	2.00
46	**Modular Face plate (2 module)** Providing & fixing Modular cover plate of anchor make Roma series - 2 module	EA	2.00
47	**Modular Face plate (3 module)** Providing & fixing Modular cover plate of anchor make Roma series - 3 module	EA	5.00

48	**Modular Face plate (4 module)** Providing & fixing Modular cover plate of anchor make Roma series - 4 module	EA	6.00
49	**Modular Face plate (6 module)** Providing & fixing Modular cover plate of anchor make Roma series - 6module	EA	20.00
50	**Modular Face plate (8 module)** Providing & fixing Modular cover plate of anchor make Roma series - 8 module	EA	20.00
51	**Face plate (9 module)** Providing & fixing Modular cover plate of anchor make Roma series - 9 module	EA	4.00
52	Providing & Fixing Recessed Light 12-18 W (100mm dia) of approved make. Colour of the body & light to be confirmed by the Architect. Vendor to submit the available options for approval. Brand - Philips & Bajaj or equivalent	EA	30.00
53	"Providing & Fixing Recessed Light 7-10 W (75mm dia) of approved make. Colour of the body & light to be confirmed by the Architect. Vendor to submit the available options for approval. Brand - Philips & Bajaj or equivalent"	Nos.	20.00
54	**S & F 18 mm thk profile light** Supply and fixing of profile LED light of 18 mm thk profile light,10watt bajaj,wipro . make including driver circuit and all associated accessories job to be completed in all respect as directed by engineer-in-charge."	RMT	20.00
55	**P/F Strip lights** Suppy and fixing of LED strip light of bajaj or equivalent make including driver circuit and all associated accessories job to be completed in all respect as directed by engineer-in-charge.	RMT	15.00
56	**C&IS, CAT5 and CAT6 Ethernet/ Telephone** C&IS, CAT5 and CAT6 Ethernet/ Telephone Cable laying through Underground including saddling, glanding, tagging at both end, termination at both end and ferruling job. Cable are to be tied up at a distance of 1 meter interval.	RMT	300.00
57	**CISE,P/laying aluminum race ways** CISE,P/laying aluminum race ways (80mm X 30mm X 2mmthk.) complete with breaking in floor for networking & electrical work, inlcuding all tools and tackles, fixing with hooks in floor, proper joints	RMT	50.00
58	Supply and Installation of floor junction boxes with top cover for above raceways of size 300mm x 300mm x 50mm x 2mm thick , fabricated out of M.S. sheets fully powder coated with removable screwed cover plates on all four sides for blocking the entry.	EA	18.00

59	**Spot light -** Providing & fixing circular led **10 watt** spot light of Phillips / Panasonic / Wipro , rate shall be inclusive of making cutout for installation and finishing the surface.	nos.	6.00
60	ELEC,Supply installation and commissioning of surface-mounted track lighting. The system shall include linear tracks fixed within the top frame or ceiling along with adjustable 5 spotlights for highlighting display elements. Work to include all necessary lighting fixtures drivers accessories connectors concealed cabling. All materials layout and quantities to be finalized based on approved design .Vendor to submit sample for approval	EA	4.00
61	Providing & Fixing Recessed Light 12-18 W (100mm dia) of approved make. Colour of the body & light to be confirmed by the Architect. Vendor to submit the available options for approval. Brand - Philips & Bajaj or equivalent	EA	10.00
62	"Providing & Fixing Recessed Light 7-10 W (75mm dia) of approved make. Colour of the body & light to be confirmed by the Architect. Vendor to submit the available options for approval. Brand - Philips & Bajaj or equivalent"	Nos.	6.00
63	CISE, Installing Testing and commissioning of Surface mounted cylindrical downlight of Bajaj Wipro . including all necessary hardware fittings etc. Job to be complete in all respect as directed by engineer-in-charge. 75mm dia Circular Recessed- 12 watts LED lights. Wiring and points shall be paid separately	nos.	10.00
64	Providing and fixing decorative round Hanging lights fittings compatible for upto 30 watt led bulb including tranpsortation at site, fixing etc complete as directed.	nos.	2.00
65	SERVICE TYPE: Providing TV points with all necessary wiring , casing and caping, race ways, ,ELCB (30 mA) , ABB, L&T, Siemens,Schneider or equivalent make etc. including all required accessories needed to complete entire electrical system in the dormitory building as per approved design and drawings and as directed by OWNER.	nos.	4.00
66	Supplying, installing, testing and commissioning of telephone point to be done with telephone outlet socket RJ-11 (jack type) and box of the specified make, including all associated accessories and hardware, job to be completed in all respect as directed by engineer-in-charge	nos.	19.00
67	PROVIDING SUPPLYING INSTALLING TESTING AND COMMISSIONING OF BEETEL LANDLINE TELEPHONE INSTRUMENT ALONG WITH CONNECTION CORD MODEL NUMBER M50	NOS.	3.00
68	PROVIDING SUPPLYING INSTALLING TESTING AND COMMISSIONING OF ALCATEL LUCENT LANDLINE TELEPHONE INSTRUMENT ALONG WITH CONNECTION CORD MODEL NUMBER ALE 20H	NOS.	10.00

69	Carpentry work in termite and water resistant commercial plywood for making cabinets, storages of depth 450 mm-600 mm depth with or without planter box and any other similar furniture in the approved layout finished with colour laminate from outside and white laminate from inside. The cost shall include all required hardware and accessories such as hinges, handles, lock and any other required to complete the job in all respect. Plywood make century, greenply or equivalent	sqm	30.00
70	Same as ITEM NO. 69 (above) with flexiply backing	sqm	5.00
71	**P&I Charcoal louvers**/ cladding with 9/12 mm ply backing in various shapes and texture as approved.Vendor to submit catalogue of various manufacturers for sample approval and submit the physical sample of the models requested by Architect for final approval. The cost shall include all required hardware, accessories and any other required to complete the job in all respect.	sqm	10.00
72	Fluted/Louvered MDF Panelling/ cladding with 9/12 mm ply backing in various shapes and texture as approved.Vendor to submit catalogue of various manufacturers for sample approval and submit the physical sample of the models requested by Architect for final approval. The cost shall include all required hardware, accessories and any other required to complete the job in all respect.	SQM	5.00
73	**P&F Acoustic Paneling** "Acoustic Paneling on Walls & Ceiling PROVIDING AND FIXING NONWOVEN POLYSTER FIBER WALL PANELS covered in fabric of approved texture & different pattern with 9mm ply backing on ceiling or wall with required supporting system inclusive of manpower, material, tools required, transportation, scaffolding,etc. PLYWOOD MAKE CENTURY, GREENPLY	sqm	15.00
74	Providing and fixing circular acoustic ceiling float panels , NRC ≥ 0.80, suspended using GI wire suspension system complete with clips, anchors, and accessories as per manufacturer's specification and architect's approval.Panels to be factory-finished in approved colours and suspended using galvanized steel wire suspension system with adjustable height clips and ceiling anchors. Make-techno acoustic,uniacoustic,saint gobain or approved equivalent. Diameter-600mm	EA	4.00

75	12mm thk ply panelling (witout finish) "P/F 12 MM THK WALL PANELLING, P/F OF 12 MM THK PLY BOARD WALL/COLUMN PANELLING WITH ALL REQUIRED BACK SUPPORTS /FRAMING IF REQUIRED INCLUDING NECESSARY CONSUMABLE LIKE NAILS ,SCREW ETC COMPLETE IN ALL RESPECT AS DIRECTED BY EIC INCLUDING THE COST OF REMOVING OF OLD PLY AND DISPOSAL IT OUTSIDE THE COMPANY PREMISES .RATE SHALL ALSO INCLUDE THE COST OF SHIFTING ,LOADING ,TRANSPORTATION AND UNLOADING OF MATERIALS. "	sqm	10.00
76	19mm thk ply panelling (without finish) P/F 19 MM THK WALL PANELLING, P/F OF 19 MM THK PLY BOARD WALL/COLUMN PANELLING WITH ALL REQUIRED BACK SUPPORTS/ FRAMING IF REQUIRED INCLUDING NECESSARY CONSUMABLE LIKE NAILS ,SCREW ETC COMPLETE IN ALL RESPECT AS DIRECTED BY EIC INCLUDING THE COST OF REMOVING OF OLD PLY AND DISPOSAL IT OUTSIDE THE COMPANY PREMISES .RATE SHALL ALSO INCLUDE THE COST OF SHIFTING ,LOADING ,TRANSPORTATION AND UNLOADING OF MATERIALS.	sqm	10.00
77	P/A two coats of first quality paint of internal grade of Asian make ACE / Nerolac Suraksha / ICI Dulux Super Coat or approved equivalent of approved colour & shade on aluminium window frame including one coat of primer,preparing the surface to receive the primer,any additional coat required to achieve even shade & colour etc. complete.The cost shall include all labour, materials, protecting adjoining surface,scaffolding,cleaning of glass after completion of painting work etc as directed by EIC	sqm	5.00
78	Supplying and placing in position color **back painted magnetic toughened glass writing board,** mounted on brick or gypsum wall partition with SS studs. Including all support system required for safe mounting of the glass	sqm	5.00
79	PROVIDING & FIXING 3D ACRYLIC LETTERS FOR NAMING OF SIZES AS MENTIONED BELOW ON WALL WITH APPROVED DESIGN AND COLOUR INCLUDING ALL TOOLS AND TACKLES FOR FIXING ETC COMPLETE AS DIRECTED.	nos.	30.00
80	Installing TATA POWER LOGO in Acrylic letters as per approved drawing with necessary arrangement for fixing on wall in matt finish with 25MM thk.	sqm	2.00
	Supply and placing in position natural potted plant along with plant. The plants shall be air purifying plants. Vendor to submit catalogue of various manufacturers for sample approval and submit the physical sample of the models requested by Architect for final approval.		-
81	9inch dia	Nos	20.00

82	24inch dia	Nos	10.00
83	Providing & fixing name plate and signage of size 6 inch X 6 inch made of SS in matt finish with required signage marked on it	nos.	4.00
84	Providing and fixing metal T/C patti 12mm to 20mm as direct by site in charge.Vendor to submit catalogue of various manufacturers for sample approval and submit the physical sample of the models requested by Architect for final approval.	rmt	25.00
85	Providing & fixing of teakwood decorative moulding patti of different size on surfaces such as wall, door, ceiling, etc. as approved by the architect as per design scheme. The cost shall include all necessary accessories, fittings, adhesive, finishing work etc. with polish to complete the job in all respect. 15mm thk	RMT	20.00
86	Providing & fixing of teakwood decorative moulding patti of different size on surfaces such as wall, door, ceiling, etc. as approved by the architect as per design scheme. The cost shall include all necessary accessories, fittings, adhesive, finishing work etc. with polish to complete the job in all respect. 25mm thk	RMT	20.00
87	Removing existing Laminate and applying new Laminate finish on Existing Door (without ply) Removing existing Laminate and Providing all materials and installing 1mm thk Laminate finish on ply panelling on wall, including all necessary hardware, adhesive,etc to complete job. Sealing gaps between sheets with colour and material to give monolithic look. 1mm thk coloured satin finish/ matt finish laminate to be used Merino, Green lam, Kajaria.	sqm	5.40
88	Providing and fixing custom printed one-way vision film on glass, including surface cleaning, proper alignment, and bubble-free application as per manufacturer’s specifications. Vendor shall share catalogues and design options for approval by the Owner/Architect before execution.	sqm	7.00
89	PROVIDING & FIXING OF DECORATIVE WALLPAPER ON GYPSUM PARTITION/WALL OR CEILING SURFACE AS GIVEN BY ARCHITECT OF APPROVED MAKE MARSHALL OR EQUIVALENT DESIGN WILL BE CONFIRMED BY THE ARCHITECT"	SQM	15.00
90	DECAL STICKERS - SUPPLYING AND FIXING IN POSITION DECAL STICKERS OF VARIOUS SIZES AS PER THE APPROVED SAMPLE. VENDOR TO SUBMIT ACTUAL SAMPLE OF DIFFERENT TYPES OF FOOD ITEMS AND FOOD QUOTES AND SYMBOLS DECAL STICKERS FOR APPROVAL. IF REQUIRED ARCHITECT SHALL SUBMIT THE REFERENCE IMAGE FOR EASY OF CONTRACTOR TO SUBMIT THE CATALOGUE.	Sqm	20.00

91	Supply and placing in position **photo frames or Wall art of 16" x 20"** Vendor to submit catalogue of various manufacturers for sample approval and submit the physical sample of the models requested by Architect for final approval.	Nos.	3.00
92	Providing and fixing custom printed acoustic panels on wall, 12–25 mm thick, having minimum NRC 0.75, with approved printed graphic finish, fixed using concealed framework or adhesive as per manufacturer's specification and architect's approval. Make- Uniacoustic,Techno acoustic,saint gobain	sqm	10.00
93	CISE,"Providing and fixing in position 55"" LED TV. Samsung LG or equivalent with all required assesories required to complete the work as directed by EIC"	NOS.	1.00
94	Prov And Fix Both Side Gypsum Partition Walls Using Gyprock Sound Block Board Of Required Thickness Of Saint Gobain As Per Appoved Drg Inclu Scaff./Aces,Making Cut-Out Of Req Sizes And Supp. Frame For Door Opening As Spec. In App. Drg. And Manu.Speci Using Metal Stud Frame Sections,Ceiling Sec,Conn. Clip,Drywall Screws, Anchor Bolts, Backing Strips, Includes Filling And Finishing With Jointing Compound, Joint Paper Tape And Two Coats Of Drywall Top Coat As Spec In Speci.Com App. Drg & Manu.Spec.	SQM	200.00
95	Aluminum powdercoated Louvers (50mm x 50mm) Vertical and horizontal members with provision for planter box and powdercoated cnc cut metal sheet panel partition as per design approved by Architect. Vendor to provide samples for powdercaoting.	SQM	7.00
96	**P/F Executive chairs** P/F office executive chairs .Medium Back Revolving Chair, Upholstered with stain resistant comfortable and breathable fabric ,tilt mechanism that allows the seat and backrest to tilt back and lock in position.Pneumatic height adjustment lever to customize the chair#s height to the user#s preference. Built-in lumbar support,supports weights up to 100-120 kg ,5 wheel smooth-rolling casters suitable for both carpeted and hard floors.BIS certified, BIFMA,GREENGUARD Certified Full 360-deg. swivel	Nos.	28.00

97	"P/S/F Conference table (SIZE : 4500 X 1350) Carpentry work for making conference table in termite resistant commercial plywood in the approved layout finished with decorative colour laminate finish. Including the under structure made in aluminum powdercoated finish. The cost shall include all required hardware and accessories such as hinges, handles, lock and any other required to complete the job in all respect. Provision for electrical box to be done as per design. Plywood make century, greenply or equivalent.Laminate make-Merino, Green lam, Kajaria.	Nos.	1.00
98	Hydraulic Workstations Specifications: Table Top: 25mm thick Pre laminate particle board with 2mm PVC edge lipping on all exposed edges Screen: 18mm fabric screen with Al Trims having magnetic strip fixed on the studs with gap of 50/75mm from the table top edges Support: MS powder coated motorised height adjustable under structure with height varying from 600-1250mm. Wire Management: 450mm Alumninium flip up and provision to mount swicthes and sockets on PVC cable dump & vertebra for wire uptake from MS cable tray fixed below the under structure and wire entry cover for wire intake from floor to cable tray. *Fixed Screen 1050 HT From Floor Level SHADE : Grey F 126	Nos.	8.00
99	High standing seating stools with leatherite seatsand adjustable height lever	Nos.	4.00
100	High Standing Table - Viak, Urban Ladder, pepprfry, wakefit, woodenstreet	Nos.	2.00
101	Meeting Pod with acoustic Panel (1800x 1800x 1200) (4 seater)	Nos.	2.00
102	Center table for meeting pod (300 to 400 mm wide x 800 in length)	Nos.	2.00
103	CISE,Providing and fixing Bar stools with back support Brand Pocho Living Premium Teakwood Acrylic Polish Fabric Upholstery (Without Fabric)(0.51 x 0.48 x 0.952 M) inlcuding lifting shifting transportation at site etc completed Terra Waves Ivory Shade in FabriCare D'Decor for Internal Fabric)	Nos.	2.00
104	Phone Booth with ledgeinside, acoustic walls and glass door, (1 m to 1.2 m sides) and	Nos.	4.00

105	Supply and delivery and installation of Leatherette 2+1+1 seater Sofa upholstered in high-quality leatherette fabric with a robust solid neem wood frame finished in garnet red/tan color as approved by the Engineer-in-Charge and come complete with two accessory cushions The product shall be pre-assemb led complying with quality standards and warranty of 12 months against manufacturing defects Installation and positioning shall be c arried out as per manufacturer#s guidelines and to the entire satisfaction of the Engineer-in-Charge Make - Viak, Urban Ladder, pepprfry, wakefit, woodenstreet	Nos.	1.00
106	Supply, delivery and installation of Glass top coffee table of 450mm dia (circular) or 450 mm x 600 mm (rectilinear) with powder coated metal legs. The product shall be pre-assemb led complying with quality standards and warranty of 12 months against manufacturing defects Installation and positioning shall be carried out as per manufacturer#s guidelines and to the entire satisfaction of the Engineer-in-Charge Make - Urban Ladder, pepprfry, wakefit, woodenstreet	Nos.	1.00
107	"Providing Storage unit for pedestal storage Dimension : 750 X 450 X 750 H # Pedestal storage : STR-MP-TT"	EA	12.00
108	providing and installing in position split Air conditioner (Capacity 1.5 Ton) of make blue star, voltas carrier or equivalent. Quote shall include all accessories required to complete the job in all respect.	No	4.00
109	Providing services for modification of Exiting ducts, Scope include 1. Modification of duct as per requirement 2. Removal and replacement of Damaged duct 3. Providing Canvas at Required location 4. Taking AC unit in Service with all required arrangements	EA	1.00

LOT 2 - Refurbishment of Project site office for Dharavi Mahalaxmi cable project

Sr. No.	Item Description	Unit	Quantity
1	**Dismantling of false ceiling** Dismantling and listing of all type of ceiling (monolythic, grid type etc) at all levels and locations and including stacking and listing of serviceable materials to any distance at scrap yard with in compound and disposal of unserviceable material to outside of building to the designated place within all leads or disposal of debris to designated place by local municipal corporation as per direction of Engineer-in-charge, rate shall be inclusive of man, material, tools such as ladder, hacksaw etc steel scaffolding, disposal of debris to designated place by local municipal corporation.	sqm	200.00
2	**Careful removal of fix furniture and reinstallation** Providing all tools and tackles for careful uninstallation of fix furniture including its supports and framings at all heights along with necessary scaffolding/platform arrangement, stacking at the designated location as directed by site engineer, disposing of the debrise at approved municipal corporation area, transportation lifting shifting etc complete as directed. Reinstallation of the fix furniture at designated position including provision and supply of all necessary tools and hardware required. as per the final design scheme	LS	1
3	**Removal of loose furniture** Providing all tools and tackles for careful uninstallation of loose furniture including its supports and framings at all heights along with necessary scaffolding/platform arrangement, stacking at the designated location as directed by site engineer, disposing of the debrise at approved municipal corporation area, transportation lifting shifting etc complete as directed.	LS	1
4	**Careful Dismantling and listing of electrical** fixtures such as lights, fan, Television, desktops, switch boards, sockets and hardware, AC or any other electrical equipment etc. and casing caping including wiring all complete including stacking of serviceable materials to any distance at scrap yard with in compound and disposal of unserviceable material disposing of the debrise at approved municipal corporation area, transportation lifting shifting etc complete as directed by Engineer-in-charge.	LS	1.00
5	**Careful Dismantling of doors and windows** Providing all tools and tackles for dismantling of door and windows including its supports and framings at all heights along with necessary scaffolding/platform arrangement, stacking at the designated location as directed by site engineer, disposing of the debrise at approved municipal	sqm	10.00

	corporation area, transportation lifting shifting etc complete as directed by Engineer in charge		
6	BREAKING AND REMOVAL OF OLD TILE/DADO/SKIRTING, INCLUDING PLASTER, ALL LEAD, LIFT & SCAFFOLDING, MAINTAINING HOUSEKEEPING, DISPOSAL OF DEBRIS WITHIN PREMISES ETC, AND HAVE TO RETURN ALL USABLE ITEM BACK TO TATA POWER STORES BY PREPARING RFW COMPLETE INCLUDING TRANSPORTATION AND DISPOSAL OF MATERIAL	sqm	200.00
7	**Acrylic Emulsion paint of internal grade:** Providing and applying one coat of sealant along with anti fungus treatment followed by one coat of cement primer filling up the crevices & holes including making full palti of painters putty and making the surfaces smooth and even with best quality painters putty and, applying primer on prepared surface and finishing with two coats of approved quality paint at all heights with Acrylic Emulsion paint (Internal quality) of first quality having VOC contain less tha 50 gm/lit of Asian make ACE / Nerolac Suraksha / ICI Dulux Super or of approved manufacturere, in approved shades.#Item includes providing & erecting steel scaffolding preparing the surface by scraping, sand papering, cleaning, solvent cleaning wherever required to remove oil/grease & painting all the internal, external walls, concrete surfaces, masonry surfaces with plaster or pointing, ceilings, chajjahs, fins, pardis, steel surfaces, wooden surfaces etc will be painted as per existing shade or as per the shade approved approved by owner at all heights.	sqm	200.00
8	Providing and fixing 600mm x 600mm size and 12 mm thick Vitrified tiles of Nitco/ Kajaria / RAK approved quality and shade as per below mentioned sizes in flooring on a 20 mm thick bedding of 1:3 cement mortar and jointed with white/ coloured cement slurry, cutting of tiles to required size, cleaning, curing, etc. complete.	sqm	200.00
9	Providing and fixing 100 mm skirting of specified material on 20 mm thick bedding of 1:4 cement mortar and jointed with white/ matching coloured cement slurry, cutting of tiles to required size, cleaning, curing, etc. complete.	sqm	40.00
10	PF POWDER COATED AC GRILLS AC	sqm	28.00

11	Providing and fixing in position minimum 10-12 mm Thk. clear toughened glass partition of st. gobain, modiguard. Glass to be fixed with framing sections anodised black coated Aluminum Partition Frame in wall and floor including all required accessories and hardware etc. required to complete the job in all respect. All exposed edges of the glass shall be machine polished. All glass-to-glass joints to be sealed with pre-approved sillicon sealants.	SQM	50
12	Providing & fixing of **Aluminium Box section of size -100 X 50 mm** in staright & curved pattern as per the design with powder coated as directed by Architect including all necessary hardware.	RM	140.00
13	**P/F Decorative glass film** Providing & fixing in position decorative glass film of Make-Garware. Contractor to submit catalogue of various design and patterns for approval."	M2	30.00
14	Providing and fixing in position solid flush door with Ply board and laminate finish complete including and all other necessary fixtures and fittings heavy duty railway type hinges etc.	SQM	5
15	Providing and fixing both sided gypsum Partition walls using Gyprock soundblock board of required thickness of saint Gobain or equivalent as per approved drawings including scaffolding/access, making cut-out of required sizes and supporting framework for door opening as specified in approved drawings and manufacturer specification using metal stud frame sections ,ceiling sections , connecting clip, drywall screws, anchor bolts, backing strips, includes filling and finishing with Jointing compound, Joint Paper tape and two coats of Drywall Top Coat as specified in specification , etc.all complete as per the the approved drawings and Manufacturer specifications and engineering drawings.	SQM	10
16	P/F of single / double leaf framed glass door with minimum 12mm thk. glass toughened by horizontal process of St. gobain, modi guard make.the door shall be with frame in MS/Ply/Wood & incl. all necessary hardware such as using patch fittings,double action hydraulic heavy duty floor spring IS:6315, door handle on both sides incl.cost of cutting floors as required.All hardwares shall be of Godrej, Dorma.Note: Hardware required:H Type SS satin finish push pull door handle for door.	SQM	10

17	Providing all materials and fixing **monolithic Gypsum board FALSE CEILING** conforming to IS 2095, at all heights and facia including providing and fixing of framework as spelled out in Saint Gobain,armstrong . manufacturer catalogue. Bidder to provide adequate steel sections (Channels, I or T sections) and hanger supports to cater to the false ceiling loads. OWNER would check the design and adequacy and has the right to reject if found inadequate. Nothing extra shall be paid for making openings for AC grills, smoke detectors, electrical fixtures etc. The cutouts shall be provided with perimeter channel of adequate size of 0.5 mm thk. all around and shall be supported suitably. Vertical / inclined face shall be measured above 300 mm high only. For payment purpose false ceiling shall be measured in plan only.	Sqm	120.00
18	Providing and fixing of **ACOUSTIC BUILT Seamless Acoustical Ceiling System** of Make Armstrong, saint gobain conforming to IS 2095, at all heights and facia including providing and fixing of framework as spelled out in Saint Gobain,armstrong . manufacturer catalogue.Nothing extra shall be paid for making openings for AC grills, smoke detectors, electrical fixtures etc. The cutouts shall be provided with perimeter channel of adequate size of 0.5 mm thk. all around and shall be supported suitably. Vertical / inclined face shall be measured above 300 mm high only. For payment purpose false ceiling shall be measured in plan only.	Sqm	15.00
19	Supplying and fixing CNC-cut decorative metal ceiling panels made from minimum 1.2 mm thick aluminium sheet (conforming to IS 737 or IS 6100) or 1.0 mm thick galvanized iron (GI) sheet (as per IS 277 or IS 513), laser or water-jet cut with smooth, deburred edges. Panels shall be factory-finished with powder coating (60–80 microns, as per IS 101/ISO 8130) or PVDF coating in approved color. Panels shall be mounted on a powder-coated mild steel (MS) or aluminium suspension framework complying with IS 2062/IS 4923 standards, suspended from RCC ceiling using galvanized iron rods and fasteners conforming to IS 4759 / IS 1367. The installation shall be as per approved reflected ceiling plans and include cut-outs for lighting fixtures, HVAC diffusers, smoke detectors, and other services. Optional acoustic perforated panels with non-woven fleece backing may be provided where specified. The metal ceiling system shall comply with fire safety requirements, achieving Class A/Class 0 fire rating as per IS 1642 and IS 302 (Part 1). The system shall be supplied, fabricated, and installed complete with all materials, labor, structural supports, and final cleaning, to the satisfaction of the Engineer-in-Charge. Minimum 10-year warranty against corrosion and finish defects shall be provided	Sqm	5.00

20	**P/F of Switch boards 4 module** "Providing and fixing Switch boards of Anchor (Roma series), Havells (Oro series), MK Switches (Ivory), Legrand (Myrius White) or equivalent make required to cater all the light points, luminary, AC, TV sceens and all other electrical fixture. including all other accessories required to complete the job in all respect and as directed by engineer-in-charge. 4 module"	EA	20.00
21	**P/F of Switch boards 6 module** "Providing and fixing Switch boards of Anchor (Roma series), Havells (Oro series), MK Switches (Ivory), Legrand (Myrius White) or equivalent make required to cater all the light points, luminary, AC, TV sceens and all other electrical fixture. including all other accessories required to complete the job in all respect and as directed by engineer-in-charge. 6module"	EA	20.00
22	**P/F of Switch boards 8 module** "Providing and fixing Switch boards of Anchor (Roma series), Havells (Oro series), MK Switches (Ivory), Legrand (Myrius White) or equivalent make required to cater all the light points, luminary, AC, TV sceens and all other electrical fixture. including all other accessories required to complete the job in all respect and as directed by engineer-in-charge. 8 module"	EA	2.00
23	**P/F of Switch boards 12 module** "Providing and fixing Switch boards of Anchor (Roma series), Havells (Oro series), MK Switches (Ivory), Legrand (Myrius White) or equivalent make required to cater all the light points, luminary, AC, TV sceens and all other electrical fixture. including all other accessories required to complete the job in all respect and as directed by engineer-in-charge. 12 module"	EA	1.00
24	**P/F of Switch boards 16 module** "Providing and fixing Switch boards of Anchor (Roma series), Havells (Oro series), MK Switches (Ivory), Legrand (Myrius White) or equivalent make required to cater all the light points, luminary, AC, TV sceens and all other electrical fixture. including all other accessories required to complete the job in all respect and as directed by engineer-in-charge. 16 module"	EA	4
25	**1.5 mm wiring** "1.5 mm wiring Installation of mains wiring including supply of 1X1CX2.5 mM2 + 2X1CX1.5 mM2 copper wire for socket outlet point in 25 mm medium gauge rigid PVC conduits as concealed manner, modular switch board, earthing with copper wire laid inside the conduit etc. Supply and laying of 25 mm PVC conduit is not included in this item."	RMT	500.00
26	**2.5 mm wiring** "2.5 mm wiring Installation of mains wiring including supply of 2X1CX2.5 mM2 + 1X1CX1.5 mM2 copper wire in 25 mm medium gauge rigid PVC conduits as concealed manner, modular switch board, earthing with copper wire laid inside the conduit etc. Supply and laying of 25 mm PVC conduit is not included in this item. Mains wiring is defined as necessary wiring from distribution board to respective switch boards and	RMT	1,000.00

	modular 5/15A switch socket units."		
27	Providing & laying **4 sqmm 3 pair wire** of approved brand Polycab including PVC conduit where required, all tools and tackles, laying etc omplete as direced.	RMT	100.00
28	**6 Amp switch** "6 Amp switch Providing & fixing 6A single pole one way switch of Anchor make Roma series, rate shall be inclusive of man, material, transportation & installation along with connection to wiring"	EA	50
29	**6 Amp socket** "6 Amp socket Providing & fixing 6 A Anchor make Roma series sockets, rate shall be inclusive of man, material, transportation & installation along with connection to wiring"	EA	40
30	**16 Amp switch** "16 Amp switch Providing & fixing 16 amp switch of Anchor make Roma series or Legrand make Myrius white series, rate shall be inclusive of man, material, transportation & installation along with connection to wiring"	EA	12
31	**16 Amp socket** "16 Amp socket Providing & fixing 16 A Anchor make Roma series sockets, rate shall be inclusive of man, material, transportation & installation along with connection to wiring"	5.00	12
32	**P/F 16 Amp RCCB** Prov & installating 16 Amp RCCB of Anchor / L & T / Havells / equivalent make including connection with wire	EA	5
33	**S & I of RCCB 2P 20A 30mA** Supply, Installation, Testing and commissioning of RCCB 2P 20A 30mA	EA	2
34	**Concealed Box (2 module)** , Providing & fixing concealed modular PVC / GI box of Anchor make - 2 module	EA	5.00
35	**Concealed Box (3 module)** Providing & fixing concealed modular PVC / GI box of Anchor make - 3 module	EA	5.00
36	**Concealed Box (4 module)** Providing & fixing concealed modular PVC / GI box of Anchor make - 4 module	EA	6.00
37	**Concealed Box (6 module)** Providing & fixing concealed modular PVC / GI box of Anchor make - 6 module	EA	20.00
38	**Concealed Box (8 module)** Providing & fixing concealed modular PVC / GI box of Anchor	EA	4.00

	make - 8 module		
39	**Concealed box (9 module)** Providing & fixing concealed modular PVC / GI box of Anchor make - 9 module	EA	2.00
40	**Modular Face plate (2 module)** Providing & fixing Modular cover plate of anchor make Roma series - 2 module	EA	2.00
41	**Modular Face plate (3 module)** Providing & fixing Modular cover plate of anchor make Roma series - 3 module	EA	5.00
42	**Modular Face plate (4 module)** Providing & fixing Modular cover plate of anchor make Roma series - 4 module	EA	6.00
43	**Modular Face plate (6 module)** Providing & fixing Modular cover plate of anchor make Roma series - 6module	EA	20.00
44	**Modular Face plate (8 module)** Providing & fixing Modular cover plate of anchor make Roma series - 8 module	EA	20.00
45	**Face plate (9 module)** Providing & fixing Modular cover plate of anchor make Roma series - 9 module	EA	4.00
46	**C&IS, CAT5 and CAT6 Ethernet/ Telephone** C&IS, CAT5 and CAT6 Ethernet/ Telephone Cable laying through Underground including saddling, glanding, tagging at both end, termination at both end and ferruling job. Cable are to be tied up at a distance of 1 meter interval.	RMT	500
47	**CISE,P/laying aluminum race ways** CISE,P/laying aluminum race ways (80mm X 30mm X 2mmthk.) complete with breaking in floor for networking & electrical work, inlcuding all tools and tackles, fixing with hooks in floor, proper joints	RMT	35
48	**floor junction boxes** S & I Of Floor Junction Boxes With Top Cover For Above Raceways Of Size 300Mm X 300Mm X 50Mm X 2Mm Thick , Fabricated Out Of S.S. Sheets With Removable Screwed Cover Plates On All Four Sides For Blocking The Entry, This Should Be Fluched With Floor Level	EA	15
49	"Providing & Fixing Recessed Light 12-18 W (150mm dia) of approved make. Colour of the body & light to be confirmed by the Architect. Vendor to submit the available options for approval. Brand - Philips & Bajaj or equivalent	EA	30
50	"Providing & Fixing Recessed Light 7-10 W (75mm dia) of approved make. Colour of the body & light to be confirmed by the Architect. Vendor to submit the available options for approval. Brand - Philips & Bajaj or equivalent"	Nos.	8

51	**S & F 18 mm thk profile light** "18 mm thk profile light Supply and fixing of profile LED light of bajaj . make including driver circuit and all associated accessories job to be completed in all respect as directed by engineer-in-charge."	RMT	15.00
52	**S & F 35 mm thk profile light** "35 mm thk profile light Supply and fixing of profile LED light of bajaj . make including driver circuit and all associated accessories job to be completed in all respect as directed by engineer-in-charge."	RMT	50.00
53	**P/F Strip lights** Suppy and fixing of LED strip light of bajaj or equivalent make including driver circuit and all associated accessories job to be completed in all respect as directed by engineer-in-charge.	RMT	15.00
54	Suppy and fixing of Spot light of bajaj/philips/wipro make including driver circuit and all associated accessories job to be completed in all respec as directed by engineer-in-charge.	nos.	6.00
55	Providing and fixing decorative round Hanging lights fittings compatible for upto 30 watt led bulb including tranpsortation at site, fixing etc complete as directed.	nos.	2.00
56	Providing TV points with all necessary conceled wiring,MCB of GE Power, or ABB, L&T, Siemens, Schneider . make etc. including all required accessories needed to complete entire electrical system in the dormitory building as per approved design and drawings and as directed by OWNER.	nos.	4.00
57	Supplying, installing, testing and commissioning of telephone point to be done with telephone outlet socket RJ-11 (jack type) and box of the specified make, including all associated accessories and hardware, job to be completed in all respect as directed by engineer-in-charge	nos.	25.00
58	Carpentry work in termite and water resistant commercial plywood for making cabinets, storages of depth 450 mm-600 mm depth with or without planter box and any other similar furniture in the approved layout finished with colour laminate from outside and white laminate from inside. The cost shall include all required hardware and accessories such as hinges, handles, lock and any other required to complete the job in all respect. Plywood make century, greenply or equivalent	sqm	10
59	"Providing, fabricating, and installing display cabinet using 19mm BWP plywood, finished with 1mm laminate of approved shade. Shutters shall be made of 6mm toughened clear glass, fixed with approved soft-close hinges and handles. Cabinet shall include internal shelving as per design and integrated 3W–5W COB LED lights (Philips/Wipro/Havells or equivalent) for illumination, including wiring and drivers. All materials and workmanship shall conform to relevant IS standards. Vendor shall submit shop drawings and material samples for approval prior to execution. Installation shall be completed in all respects as per design and to the satisfaction of the	sqm	10

	Architect/Engineer-in-Charge."		
60	Providing all materials and installing **textured MDF** sheet of minimum 12mm thick as wall panelling, including providing and installing base frame in metal sections of approproiate thickness. Sealing gaps between sheets with matching colour and material to give mnolithic look.	sqm	10
61	**P&I Charcoal louvers/ Fluted panel** Fluted/Louvered MDF Panelling/ cladding with 9/12 mm ply backing in various shapes and texture as approved.Vendor to submit catalogue of various manufacturers for sample approval and submit the physical sample of the models requested by Architect for final approval. The cost shall include all required hardware, accessories and any other required to complete the job in all respect.	sqm	10
62	**P&F Acoustic Paneling** "Acoustic Paneling on Walls & Ceiling PROVIDING AND FIXING NONWOVEN POLYSTER FIBER WALL PANELS covered in fabric of approved texture & different pattern with 9mm ply backing on ceiling or wall with required supporting system inclusive of manpower, material, tools required, transportation, scaffolding,etc. Base rate of fabric is 400 Rs/mt PLYWOOD MAKE CENTURY, GREENPLY	sqm	20.00
63	Laminate finish on panel (without ply) Providing all materials and installing 1mm thk Laminate finish on ply panelling on wall, including all necessary hardware, adhesive,etc to complete job. Sealing gaps between sheets with colour and material to give monolithic look. 1mm thk coloured satin finish/ matt finish laminate to be used Merino, Green lam, Kajaria.	sqm	20.00
64	12mm thk ply panelling (witout finish) "P/F 12 MM THK WALL PANELLING, P/F OF 12 MM THK PLY BOARD WALL/COLUMN PANELLING WITH ALL REQUIRED BACK SUPPORTS /FRAMING IF REQUIRED INCLUDING NECESSARY CONSUMABLE LIKE NAILS ,SCREW ETC COMPLETE IN ALL RESPECT AS DIRECTED BY EIC INCLUDING THE COST OF REMOVING OF OLD PLY AND DISPOSAL IT OUTSIDE THE COMPANY PREMISES .RATE SHALL ALSO INCLUDE THE COST OF SHIFTING ,LOADING ,TRANSPORTATION AND UNLOADING OF MATERIALS. "	sqm	28.00

65	19mm thk ply panelling (without finish) P/F 19 MM THK WALL PANELLING, P/F OF 19 MM THK PLY BOARD WALL/COLUMN PANELLING WITH ALL REQUIRED BACK SUPPORTS/ FRAMING IF REQUIRED INCLUDING NECESSARY CONSUMABLE LIKE NAILS ,SCREW ETC COMPLETE IN ALL RESPECT AS DIRECTED BY EIC INCLUDING THE COST OF REMOVING OF OLD PLY AND DISPOSAL IT OUTSIDE THE COMPANY PREMISES .RATE SHALL ALSO INCLUDE THE COST OF SHIFTING ,LOADING ,TRANSPORTATION AND UNLOADING OF MATERIALS.	sqm	20
66	Supplying and placing in position color **back painted magnetic toughened glass writing board,** mounted on brick or gypsum wall partition with SS studs. Including all support system required for safe mounting of the glass	sqm	10.00
67	Acrylic letters - 6 inches Providing, supplying & fixing 6 mm thick 6 inch high Acrylic letters of approved shade & font	nos.	50.00
68	Supply and placing in position natural potted plant along with plant. The plants shall be air purifying plants. Vendor to submit catalogue of various manufacturers for sample approval and submit the physical sample of the models requested by Architect for final approval. 9inch dia	Nos	4
69	Supply and placing in position natural potted plant along with plant. The plants shall be air purifying plants. Vendor to submit catalogue of various manufacturers for sample approval and submit the physical sample of the models requested by Architect for final approval. 24 inch dia	Nos	2
70	Providing & fixing name plate and signage of size 6 inch X 6 inch made of SS in matt finish with required signage marked on it	nos.	5
71	Providing and fixing metal T/C patti 12mm to 20mm as direct by site in charge.Vendor to submit catalogue of various manufacturers for sample approval and submit the physical sample of the models requested by Architect for final approval.	rmt	15
72	Providing & fixing of teakwood decorative moulding patti of different size on surfaces such as wall, door, ceiling, etc. as approved by the architect as per design scheme. The cost shall include all necessary accessories, fittings, adhesive, finishing work etc. with polish to complete the job in all respect. 15mm thk	RMT	10
73	Providing & fixing of teakwood decorative moulding patti of different size on surfaces such as wall, door, ceiling, etc. as approved by the architect as per design scheme. The cost shall include all necessary accessories, fittings, adhesive, finishing work etc. with polish to complete the job in all respect. 25mm thk	RMT	10

74	**P/F Wall clock for waiting area & conference room** Wall clock-Providing, supplying & placing in position Wall clock of approved by architect so as to complete the job. Base rate - 3500 Rs.	EA	2.00
75	**P/F Wall clock in office area,Cabin** Wall clock-Providing, supplying & placing in position Wall clock of approved by architect so as to complete the job. Base rate - 500 Rs.	EA	6.00
76	Dustbins Providing, supplying & placing in position perforated SS dustbins of 12 inch dia as per approved architectural palette	nos.	25
77	Providing & Fixing of **decorative Wallpaper** on gypsum partition/wall or ceiling surface as given by Architect of approved make Marshall or equivalent Design will be confirmed by the Architect	M2	40.00
78	**Decal stickers** - supplying and fixing in position decal stickers of various sizes as per the approved sample. Vendor to submit actual sample of different types of quotes and symbols decal stickers for approval. If required Architect shall submit the reference image for easy of contractor to submit the catalogue	Sqm	20
79	Supply and placing in position **photo frames or Wall art of 16" x 20"** Vendor to submit catalogue of various manufacturers for sample approval and submit the physical sample of the models requested by Architect for final approval.	Nos.	4
80	Making of 5 mm thk groove on wall/ceiling surface prepared with putty/pop to proper angle, line, level to receive paint.	rmt	40
81	**Providing and Fixing of LOGO in SS letters** with necessary arrangement for fixing on wall in matt finish, Tata blue colour. (Logo and letter height as mentioned below) Logo height 280mm, 25 mm thick	EA	1.00
82	**Providing and Fixing of LOGO in SS letters** with necessary arrangement for fixing on wall in matt finish, Tata blue colour. (Logo and letter height as mentioned below) Logo Letter height: 140mm,25mm thk	EA	13.00
83	**P/F 4 SEATER CONFERENCE ROOM TABLE** "Providing, supplying, and placing in position conference table 4 SEATER CONFERENCE ROOM TABLE, Access flap required. 1) Size: 900mm diameter (circular shape) Thickness of the Board - 25 MM. 2) Specification: Prelaminated Particle Board- Material will be Prelaminated Particle Board (PLPB shall be confirming to IS 12823 : 1990 (Reaffirmed 2009) grade I and Type I) with laminate of marino, century, greenlam, signature finish Table top. 3) Powder coated metallic under structure. Thickness of under section as per manufacturere design and as required for table stability. However it should not be less than 50X50 MM THK . Or 60x30 mm thck METAL LEGS "	nos	1

84	Providing, supplying, and placing in position conference table 13 SEATER CONFERENCE ROOM TABLE, Access flap is required. 1) Size:3600(L)x1200(B)x750(H) mm(Rectangular shape), Specification: Laminate finish (Elegant teak) Table top, 2) Worktop of 25 mm thick prelaminated (Particle Board-Material will be Prelaminated Particle Board (PLPB shall be confirming to IS 12823 : 1990 (Reaffirmed 2009) grade I and Type I) with laminate of marino, century, greenlam, signature laminate finished with 2 mm thk.PVC edgebanding . 3) Understructure section as per manufacturere design and as required for table stability. However it should not be less than 50X50 MM THK . Or 60x30 mm thck METAL LEGS MS CRCA with supporting Tie members of 20x40 mm thk.finished with powder coating. 4)Intermediate leg cable riser with perforated modesty panel & 3-4 Pop up BOX is provided.	EA	1
85	Providing, fabricating, projection and installation of powder coated Aluminum (approved shade and texture) hollow box section of 100mm x 50 mm size and 3 to 4 mm thick, erected as per shop drawing and details shared by the architect in guidance of engineer-in-charge.Vendor to submit catalouges/sample for approval	RMT	10
86	**P/F Executive chairs** P/F office executive chairs .Medium Back Revolving Chair, Upholstered with stain resistant comfortable and breathable fabric ,tilt mechanism that allows the seat and backrest to tilt back and lock in position.Pneumatic height adjustment lever to customize the chair#s height to the user#s preference. Built-in lumbar support,supports weights up to 100-120 kg ,5 wheel smooth-rolling casters suitable for both carpeted and hard floors.BIS certified, BIFMA,GREENGUARD Certified Full 360-deg. swivel	Nos.	44.00
87	Supply and delivery and installation of Leatherette Sofa 1-seater chair model upholstered in high-quality leatherette fabric with a robust solid neem wood frame finished in garnet red/tan color as approved by the Engineer-in-Charge and come complete with two accessory cushions The product shall be pre-assemb led complying with quality standards and warranty of 12 months against manufacturing defects Installation and positioning shall be c arried out as per manufacturer#s guidelines and to the entire satisfaction of the Engineer-in-Charge Make - Urban Ladder, pepprfry, wakefit, woodenstreet	Nos.	2.00

88	Supply and delivery and installation of Leatherette Sofa 2-seater model upholstered in high-quality leatherette fabric with a robust solid neem wood frame finished in garnet red/tan color as approved by the Engineer-in-Charge and come complete with two accessory cushions The product shall be pre-assemb led complying with quality standards and warranty of 12 months against manufacturing defects Installation and positioning shall be c arried out as per manufacturer#s guidelines and to the entire satisfaction of the Engineer-in-Charge Make - Urban Ladder, pepprfry, wakefit, woodenstreet	Nos.	1.00
89	Supply, delivery and installation of Glass top coffee table of 450mm dia (circular) or 450 mm x 600 mm (rectilinear) with powder coated metal legs. The product shall be pre-assemb led complying with quality standards and warranty of 12 months against manufacturing defects Installation and positioning shall be carried out as per manufacturer#s guidelines and to the entire satisfaction of the Engineer-in-Charge Make - Urban Ladder, pepprfry, wakefit, woodenstreet	Nos.	1.00
90	**P/F Aisle Storage PLPB 1500 L** Providing aisle storage # near workstation, Providing, supplying, and placing in position storage cabinets of total 1500(L)x 450(B)x 1200(H) mm including 150mm high planters shelf & with storage shelf and shutters - Material will be Prelaminated Particle Board (PLPB shall be confirming to IS 12823 : 1990 (Reaffirmed 2009) grade I and Type I) with laminate of marino, century, greenlam, signature or equivalent as per approval. Thickness of board will be 18MM. Required Finger Groove	Nos.	5.00
91	P/S/F Smart interactive touch screen TV unit- 65 inch	Nos.	1
92	P/F Workstation single unit	EA	18
93	P/F Pedestal unit MDF	EA	18
94	P/F L shape Cubicle Single module	EA	5
95	P/F Cabin Table	EA	1.00
96	Providing services for modification of Exiting ducts, Scope include 1. Modification of duct as per requirement 2. Removal and replacement of Damaged duct 3. Providing Canvas at Required location 4. Taking AC unit in Service with all required arrangements	EA	1.00
97	P/F Head back chairs	EA	3.00

Note: Above Quantities are tentative. Tata Power reserves the right to curtailed / enhance the quantities before the placement of Purchase Order.

It may be noted that all future correspondence will be strictly done only with Interested Vendors who have done the above steps (As mentioned in section “B”) in time with Authorized Person, and only through Tata Power E-Tender System.