

**The Tata Power Company Limited Invites Tenders** through E-Tender Two-Part bidding process from interested bidders (with manufacturing / assembling facilities in India) for the following package required for its Transmission Division: -

**Procedure for Participating in Tender**

Tender Enquiry No.	Work Description	EMD (Rs.)	Tender Participation Fee (Rs.)	Last date & time for Payment of Tender Participation Fee*
CC27SB005	Outline Agreement of 3 years for Pre and Post monsoon works in Transmission Division (south Circle)	10,000 /-	2,000/-	15.00 Hrs. Monday, 18 <sup>th</sup> May 2026

**\* Interested bidder is strongly advised not to wait by above time and purchase the tender immediately to get the link for bid submission. This will enable them to communicate/raise queries against the subject tender in time.**

**Procedure for Participating in Tender. Following steps to be done before last date for purchase of tender,**

1. Interested bidder to refer to the Section C: "Pre-Qualification Requirement" (PQR).
2. Eligible and Interested Bidder to submit duly signed and stamped letter on Bidder's letterhead indicating,
  - a. Tender Enquiry number.
  - b. Name of authorized person.
  - c. Contact number.
  - d. e-mail id.
  - e. Details of submission of Tender Participation Fee.
3. Non-Refundable Tender Participation Fee, as indicated in table above, to be submitted in the form of Direct deposit in the following bank account and submit the receipt along with a covering letter clearly indicating the Tender Reference number –

Beneficiary Name – The Tata Power Co. Ltd.

Bank Name – HDFC Bank Ltd.

Branch Name – Fort Branch, Mumbai

Address – Maneckji Wadia Building, Nanik Motwani Marg, Fort, Mumbai 400023.

Branch Code – 60

Bank & Branch Code – 400240015

Account No – 00600110000763

Account type – CC

E-mail with necessary attachment of 1 and 2 above to be send to [shrushti.bhujbal@tatapower.com](mailto:shrushti.bhujbal@tatapower.com) & with copy to [vivek.mittal@tatapower.com](mailto:vivek.mittal@tatapower.com) before “Last date and time for Payment of Tender Participation Fee”.

Interested bidders to submit Tender Participation Fee and Authorization Letter before Last date and time as indicated above after which link from Tata Power E-Tender system (Ariba) will be shared for further communication and bid submission.

Please note all future correspondence regarding the tender, bid submission, bid submission date extension, Pre-bid query etc will happen only will be strictly done only with interested bidders who have done the above steps in time with Authorized Person only through Tata Power E-Tender system (Ariba). User manual to guide the bidders to submit the bid through e-Tender system (Ariba) is also enclosed.

No e-mail or verbal correspondence will be responded. All communication will be done strictly with the bidder who have done the above steps (Payment of tender fee and submission of letter with requisite details) to participate in the Tender.

Also, it may be strictly noted that once date of “Last date and time for Payment of Tender Participation Fee” is lapsed no Bidder will be sent link from Tata Power E-Tender System (Ariba). Without this link vendor will not be able to participate in the tender. Any last moment request to participate in tender will not be acknowledged.

Any payment of Tender Participation Fee / EMD by Bidder who have not done the pre-requisite within stipulated timeline will not be refunded.

Also, all future corrigendum's to the said tender, if any, will be informed on Tender section on website <https://www.tatapower.com>

**Earnest Money Deposit (EMD) is not to be submitted now and is required at a later stage along with tender submission in the form of Bank Guarantee and NEFT.**

<b>FORMAT C.1</b>					
<b>Technical Pre-Qualification Requirement and Submission Format</b>					
<b>Tender No</b>					
<b>Package Name</b> <b>Outline Agreement of 3 years for Pre post monsoon works at south zone</b>					
<b>Bidder :</b>					
<b>Note :</b> Vendor Submission / claim without suitable backup document will not be accepted and Bid is Liable for Rejection					
This format duly filled in editable Excel format has to be uploaded as Bid Submission with all relevant Backup Document					
Package Description:Outline Agreement of 3 years for Pre post monsoon works at south zone					
Tender Reference No - CC275B005					
Pre - Qualification Requirement (PQR) - Please note that the PQR is for information only and the documentary evidence to ascertain meeting of the requirement has to be submitted along with the bid and not along with the tender fee					
					<b>To be filled up by Vendor</b>
Sr No	Parameter	Tata Power Requirement	Documents to be submitted by vendor to ascertain meeting of Pre-Qualification Requirement	Vendor Submission against Tata Power PQR Requirement	Documents submitted by Vendor to ascertain meeting of Pre-Qualification Requirement
<b>1</b>	<b>2</b>	<b>3</b>	<b>4</b>	<b>5</b>	<b>6</b>
(A)	<b>Experience</b>	1. Bidder should have minimum 3 years' experience in Civil Works and Pre post monsoon works. 2. Bidder should have 3 years' experience to work in " High voltage Electrical substation Premises"	Bidder to submit credentials for supporting the noted criteria. Owner has the right to reject the bid in case it is observed that the Bidder does not meet the relevant experience for the subject works		
(B)	<b>ISO Certifications</b>	Bidder should possess ISO-9001, ISO-14001 and OHSAS-18001 / ISO-45001 Certification or they must give an undertaking for its willingness to obtain the same within 2 months of award of the work.	Bidder to submit credentials for supporting the noted criteria. Owner has the right to reject the bid in case it is observed that the Bidder does not meet the relevant experience for the subject works.		
(C)	<b>Commercial Capability</b>	Average annual turnover of the Vendor for last three financial years shall not be less than <b>Rs. 30 lakhs.</b>	Profit and Loss Statements, Balance Sheet, Cash Flow Statements for the Three (3) preceding financial years duly audited and approved by Authorized Audit Firm / CA.		

## **BOQ\_Outline Agreement of 3 years for Pre and Post monsoon works in Transmission Division (south Circle)**

### **Scope:**

The **scope of the work** consists of Civil services for Pre and Post monsoon works like Vegetation removal, Drain cleaning, SWD cleaning, Cleaning of Sheet, dewatering pumps and monsoon related works inside Operational and nonoperational Area at South Zone.

**Location** consists of Dharavi RSS, Dharavi colony, BKC RSS, BKC Tower Location 18, Antop Hill RSS and plot, Ramtekadi Colony, Sewri, Pratikshanagar and chunabhatti yard, Parel RSS, Mahalaxmi RSS, Wadala yard, Carnac and Backbay RSS.

This work is carried out as per requirement of Customer.

**Purpose** – This work is to be carried out to avoid critical conditions during monsoon.

### **Site Specific Requirement** –

1. Successful Bidder will have to deploy work force with L1, L2 & L3 Training from TATA Power Skill Development Institute as per the Policy of TATA Power Co. Ltd. All safety standard at site shall be understood and complied with Tata power Corporate Safety standards & Norms.
2. Successful bidder will deploy workforce and resources as per site situations during monsoon.

**CC27SB005 Outline Agreement of 3 years for Pre and Post monsoon works in Transmission Division (south Circle)**

Sr.No	Short Text	Long Text	Qty	Unit
1	CLEANING G I SHEET ROOF/CHAJJAHS	PROVIDING ALL NECESSARY SERVICES,TOOLS, TACKLES,MANPOWER, MATERIALS,LADDER FOR CLEANING OF G.I./PRECOATED ROOF SHEET, SLOPING RCC ROOF, CHAJJAS INCLUDING THE COST OF REMOVING OF DRY LEAVES AND DUST FROM THE ENTIRE AREA WITH THE HELP OF WIRE BRUSH & SWEEPING WITH THE BROOM. RATE SHALL INCLUDE THE COST OF INSPECTION OF RAIN WATER DOWN TAKE PIPE BY POURING OF WATER THROUGH IT . RATE SHALL ALSO INCLUDE THE COST OF DISPOSAL OF MATERIALS OUTSIDE THE COMPANY PREMISES.,	8,700	M2
2	CLEANING SW CHAMBER ANY SIZE UPTO 600MM	PROVIDING ALL YOUR TOOLS AND EQUIPMENTS ETC INCLUDING SERVICES FOR CLEANING OF INSPECTION CHAMBER OF ANY SIZE BUT UPTO DEPTH OF 600 MM INCLUDING REMOVAL OF SOLID STUFF AND DISPOSAL OF THE SAME OUTSIDE TATA POWER AND FLUSHING THE CHAMBER WITH FRESH WATER, REMOVING AND REPLACING COVERS ETC. COMPLETED AS DIRECTED BY ENGINEER IN CHARGE. NO SEPARATE PAYMENT SHALL BE MADE FOR INSPECTION OF CHAMBER.,	36	EA
3	CLEANING SW CHAMBER ANY SIZE > 600MM	PROVIDING ALL YOUR TOOLS AND EQUIPMENTS ETC INCLUDING SERVICES FOR CLEANING OF INSPECTION CHAMBER OF ANY SIZE BUT DEPTH MORE THAN 600 MM INCLUDING REMOVAL OF SOLID STUFF AND DISPOSAL OF THE SAME OUTSIDE TATA POWER AND FLUSHING THE CHAMBER WITH FRESH WATER, REMOVING AND REPLACING COVERS ETC. COMPLETED AS DIRECTED BY ENGINEER IN CHARGE. NO SEPARATE PAYMENT SHALL BE MADE FOR INSPECTION OF CHAMBER.,	22	EA
4	CLEANING SEWAGE CHAMBER UPTO 600 DEPTH	PROVIDING SERVICES FOR MANUAL CLEANING OR WITH MACHINE FOR ALL DEPTHS UPTO 600MM INCLUDING, REMOVAL AND DISPOSAL OF SOLID STUFF AT A PLACE EARMARKED FOR THE PURPOSE, FLUSHING THE CHAMBER WITH FRESH WATER INCLUDING REMOVING AND RE-PLACING THE COVERS ETC. COMPLETE AS DIRECTED.(SEWRAGE DRAIN CHAMBERS). THIS OPERATION WILL BE PAID WHEN THERE IS A OVERFLOW OF CHAMBER/ANY COMPLAINT RECEIVED. NO SEPARATE PAYMENT SHALL BE MADE FOR INSPECTION OF CHAMBER.	112	EA
5	CLEANING SEWAGE CHAMBER BEYOND 600 DEPTH	PROVIDING SERVICES FOR MANUAL CLEANING OR WITH MACHINE FOR ALL DEPTHS BEYOND 600MM INCLUDING, REMOVAL AND DISPOSAL OF SOLID STUFF AT A PLACE EARMARKED FOR THE PURPOSE, FLUSHING THE CHAMBER WITH FRESH WATER INCLUDING REMOVING AND RE-PLACING THE COVERS ETC. COMPLETE AS DIRECTED.(SEWRAGE DRAIN CHAMBERS). THIS OPERATION WILL BE PAID WHEN THERE IS A OVERFLOW OF CHAMBER/ANY COMPLAINT RECEIVED. NO SEPARATE PAYMENT SHALL BE MADE FOR INSPECTION OF CHAMBER.	36	EA
6	INSPECTION SEWAGE CHAMBER MS/RCC COVERS	PROVIDING ALL NECESSARY SERVICES INCLUDING TOOLS TACKLES,MANPOWER FOR LIFTING OF ANY SIZES CHEQUERED PLATE DRAIN COVER/RCC COVERS FOR INSPECTION OF SEWAGE CHAMBER. RATE SHALL INCLUDE THE COST OF SHIFTING AND RE-FIXING OF DRAIN COVER IN IT ORGINAL PLACE AFTER COMPLETION OF INSPECTION AS DIRECTED BY OWNER. THIS ITEM WILL BE PAID WHEN CHAMBER IS OPEN FOR INSPECTION AND FOUND CLEAN.,	15	EA
7	INSPECTION SW DRAIN COVERED CHAMBERS	PROVIDING ALL NECESSARY SERVICES INCLUDING TOOLS TACKLES,MANPOWER FOR LIFTING OF ANY SIZES DRAINS COVERED WITH CHEQUERED PLATE COVERS/GRATINGS/RCC PRECAST FOR INSPECTION OF STORM WATER DRAIN CHAMBER. RATE SHALL INCLUDE THE COST OF SHIFTING AND RE-PLACING OF CHEQUERED PLATE DRAIN COVER IN IT ORGINAL PLACE AFTER COMPLETION OF INSPECTION AS DIRECTED BY OWNER. THIS ITEM WILL BE PAID WHEN CHAMBER IS OPEN FOR INSPECTION AND FOUND CLEAN.,	22	EA

8	CLEANING OF SEWAGE DRAIN PIPELINES	PROVIDING SERVICES FOR CLEANING OF SEWAGE PIPE LINES BETWEEN TWO CHAMBERS. RATE SHALL INCLUDE PROVIDING ALL NECESSARY SERVICES (MANUAL OR MACHINE) FOR REMOVAL AND DISPOSAL OF SOLID STUFF AT A PLACE EARMARKED FOR THE PURPOSE, CLEANING WITH ROD AND FLUSHING THE CHAMBER WITH FRESH WATER INCLUDING REMOVING AND RE PLACING THE COVERS ETC. COMPLETE AS DIRECTED. THIS OPERATION WILL BE PAID WHEN THERE IS A OVERFLOW OF CHAMBER/CHOK UP OF LINE/ANY COMPLAINT RECEIVED.	464	M
9	CLEANING OF STORM WATER DRAIN PIPELINES	PROVIDING SERVICES FOR CLEANING OF STORM WATER DRAIN PIPE LINES BETWEEN TWO CHAMBERS. RATE SHALL INCLUDE PROVIDING ALL NECESSARY SERVICES (MANUAL OR MACHINE) FOR REMOVAL AND DISPOSAL OF SOLID STUFF AT A PLACE EARMARKED FOR THE PURPOSE, CLEANING WITH ROD AND FLUSHING THE CHAMBER WITH FRESH WATER INCLUDING REMOVING AND RE PLACING THE COVERS ETC. COMPLETE AS DIRECTED. THIS OPERATION WILL BE PAID WHEN THERE IS A CHOK UP IN LINE/ANY COMPLAINT RECEIVED.	145	M
10	CLEANING OF SEPTIC TANK	PROVIDING SERVICES FOR CLEANING OF SEPTIC TANKS USING NECESSARY CLEANING MATERIALS, BMC GULLEY SUCKER VEHICLE. INCLUDING REMOVING AND PLACING OF COVERS PROPERLY, ALL TOOLS AND TACKLES REQUIRED TO EMPTY OUT THE CHAMBER ETC COMPLETE AS DIRECTED. (MEASUREMENTS SHALL BE PAID ON NUMBER OF SEPTIC TANKS)	1	EA
11	CLEANING OF STORM WATER DRAIN (COVERED)	PROVIDING ALL TOOLS AND CARRYING OUT NECESSARY ARRANGEMENT ANDCLEANING OF STORM WATER DRAIN COVERED WITH RCC PRECAST COVERS/CHEQUERED PLATE/GRATING) INCLUDING REMOVAL OF STONES, PEBBELS, TREE TRUNKS, DRY LEAVES, MUCK, SILT ETC. AND INCLUDING TRANSPORTING THE SAME OUTSIDE THE TATA POWER PREMISES TO NEAREST APPROVED DUMPING YARD COMPLETED AS DIRECTED BY EIC. THE RATES SHALL ALSO INCLUDE REMOVAL OF RCC PRECAST COVERS STACKING THE SAME AT DESIGNATED LOCATION AND REFIXING THE SAME AFTER COMPLETION OF ACTIVITY. NET VOLUME OF MUCK WILL BE MEASURED AND PAID FOR.,	44	M3
12	CLEANING OF STORM WATER DRAIN (OPEN)	PROVIDING ALL TOOLS, TACKLES & CARRYING OUT NECESSARY ARRANGEMENTS FOR CLEANING OF OPEN STORM WATER DRAINS OF ANY SIZES INCLUDING REMOVAL OF STONES, TREE TRUNKS, DRY LEAVES, MUCK, SILT ETC. INCLUDING THE COST OF PLACING AND RE-PLACING OF COVER AFTER COMPLETION OF WORK RATE SHALL INCLUDE THE COST OF SHIFTING, LOADING & TRANSPORTING THE MATERIALS OUTSIDE THE OWNER PREMISES COMPLETE AS DIRECTED., NOTE: MEASUREMENT OF REMOVED MATERIALS WILL BE PAID IN CUM,	22	M3
13	REM. GRASS/VEGETATION OPNL AREA MAJOR	PROVIDING ALL YOUR TOOLS, TACKLES, EQUIPMENTS AND MAJOR SERVICES FOR REMOVAL OF VEGETATION AND WILD GROWTH/SHRUBS BY CUTTING THE ROOTS INSIDE THE OPERATIONAL AREA INCLUDING REMOVAL OF METAL, UPROOTING FROM ROOTS AND RESTORING METAL DISTURBED OR UPROOTING FROM THE GARDEN AREA, INTERNAL CREEPERS ON COMPOUND WALL/FENCING/BARBED WIRE ETC. WHICH INCLUDED NECESSARY ACTION LIKE WEEDICIDE TREATMENT TO ENSURE NO VEGETATION GROWTH AS PER WEEDICIDE STANDARD PRACTICE INCLUDING CLEANING OF ENTIRE AREA, COLLECTION OF DEBRIS AND TRANSPORTING OF CUT GRASS OUTSIDE THE OWNER'S PREMISES & COMPLETE AS DIRECTED., THE ACTIVITY WILL BE DONE ONCE BEFORE START OF MONSOON AND SHALL COMMENCE THE WORK WITHIN 2 DAYS FROM THE INTIMATION NOTICE BY CONCERNED TATA POWER ENGINEER. AFTER REMOVAL OF WILD GROWTH, DURING THE FIRST ONE MONTH PERIOD, VENDOR HAS TO ENSURE THAT THERE IS NO FORMATION OF WILD GROWTH INSIDE THE ENTIRE COMPANY PREMISES AND NO EXTRA PAYMENT WILL BE MADE FOR MAINTAINING THE COMPANY PREMISES AREA DURING THE ONE MONTH PERIOD. IF COMPLAINT OR SAFETY OBSERVATION FOR NON REMOVAL OF GRASS/VEGETATION IS RECEIVED THERE WILL BE PENALTY OF RS. 500 PER COMPLAINT WILL BE CHARGED AND WILL BE DEDUCTED FROM BILL & VENDOR NEED TO ENSURE ZERO GRASS/WILD GROWTH CONDITIONS AND REPORTS.	1	EA

14	REM. GRASS/VEGETN OPN AREA MINOR MONSOON	<p>PROVIDING ALL YOUR TOOLS, TACKLES, EQUIPMENTS AND MINOR SERVICES FOR REGULAR INSPECTION OF AREA FOR ANY VEGETATION GROWTH AND ARRANGE MANPOWER IMMEDIATELY FOR REMOVAL OF VEGETATION AND WILD GROWTH/SHRUBS, IF FOUND BY CUTTING THE ROOTS INSIDE THE OPERATIONAL AREA INCLUDING REMOVAL OF METAL, UPROOTING FROM ROOTS AND RESTORING METAL DISTURBED OR UPROOTING FROM THE GARDEN AREA, INCLUDING INTERNAL CREEPERS ON COMPOUND WALL/FENCING/BARBED WIRE (CREEPERS SHOULD BE REMOVED IMMEDIATLY WHEN IT IS ON GROUND) ETC.WHICH INCLUDED NECESSARY ACTION LIKE WEEDICIDE TREATMENT TO ENSURE NO VEGETATION GROWTH AS PER WEEDICIDE STANDARD PRACTICE INCLUDING CLEANING OF ENTIRE AREA, COLLECTION OF DEBRIS AND TRANSPORTING OF CUT GRASS OUTSIDE THE TATA POWER PREMISES &amp; COMPLETE AS DIRECTED AND SHALL COMMENCE THE WORK WITHIN 2 DAYS FROM THE INTIMATION NOTICE BY CONCERNED TATA POWER ENGINEER. AFTER REMOVAL OF WILD GROWTH,DURING THE ENTIRE ONE MONTH PERIOD, VENDOR HAS TO ENSURE THAT THERE IS NO FORMATION OF WILD GROWTH INSIDE THE ENTIRE OPERATIONAL PREMISES AND NO EXTRA PAYMENT WILL BE MADE FOR MAINTAINING THE COMPANY PREMISES AREA DURING THE ONE MONTH PERIOD. IF COMPLAINT RECEIVED FROM DIVISION THERE WILL BE PENALTY OF RS. 500 PER COMPLAINT WILL CHARGED AND WILL BE DEDUCTED FROM BILL &amp; VENDOR NEED TO ENSURE ZERO GRASS/WILD GROWTH CONDITIONS AND REPORTS. (DURING MONSOON PERIOD)</p>	5	MON
15	REM GRASS/VEGETN OPNAREA MINOR NON MONSO	<p>PROVIDING ALL YOUR TOOLS, TACKLES, EQUIPMENTS AND MINOR SERVICES FOR REGULAR INSPECTION OF AREA FOR ANY VEGETATION GROWTH AND ARRANGE MANPOWER IMMEDIATELY FOR REMOVAL OF VEGETATION AND WILD GROWTH/SHRUBS, IF FOUND BY CUTTING THE ROOTS INSIDE THE OPERATIONAL AREA INCLUDING REMOVAL OF METAL, UPROOTING FROM ROOTS AND RESTORING METAL DISTURBED OR UPROOTING FROM THE GARDEN AREA, INCLUDING INTERNAL CREEPERS ON COMPOUND WALL/FENCING/BARBED WIRE (CREEPERS SHOULD BE REMOVED IMMEDIATLY WHEN IT IS ON GROUND) ETC. WHICH INCLUDED NECESSARY ACTION LIKE WEEDICIDE TREATMENT TO ENSURE NO VEGETATION GROWTH AS PER WEEDICIDE STANDARD PRACTICE INCLUDING CLEANING OF ENTIRE AREA, COLLECTION OF DEBRIS AND TRANSPORTING OF CUT GRASS OUTSIDE THE TATA POWER PREMISES &amp; COMPLETE AS DIRECTED AND SHALL COMMENCE THE WORK WITHIN 2 DAYS FROM THE INTIMATION NOTICE BY CONCERNED TATA POWER ENGINEER. AFTER REMOVAL OF WILD GROWTH,DURING THE ENTIRE ONE MONTH PERIOD, VENDOR HAS TO ENSURE THAT THERE IS NO FORMATION OF WILD GROWTH INSIDE THE ENTIRE OPERATIONAL PREMISES AND NO EXTRA PAYMENT WILL BE MADE FOR MAINTAINING THE COMPANY PREMISES AREA DURING THE ONE MONTH PERIOD. IF COMPLAINT RECEIVED FROM DIVISION THERE WILL BE PENALTY OF RS. 500 PER COMPLAINT WILL CHARGED AND WILL BE DEDUCTED FROM BILL &amp; VENDOR NEED TO ENSURE ZERO GRASS/WILD GROWTH CONDITIONS AND REPORTS. (DURING NON MONSOON PERIOD)</p>	6	MON

16	REM. GRASS/VEGETATION NONOPNL AREA MAJOR	<p>PROVIDING ALL YOUR TOOLS, TACKLES, EQUIPMENTS AND MAJOR SERVICES FOR REMOVAL OF VEGETATION AND WILD GROWTH/SHRUBS BY CUTTING THE ROOTS INSIDE THE COMPANY PREMISES IN NON-OPERATIONAL AREA INCLUDING REMOVAL OF METAL, UPROOTING FROM ROOTS AND RESTORING METAL DISTURBED OR UPROOTING FROM THE GARDEN AREA, INTERNAL CREEPERS ON COMPOUND WALL/FENCING/BARBED WIRE ETC. WHICH INCLUDED NECESSARY ACTION LIKE WEEDICIDE TREATMENT TO ENSURE NO VEGETATION GROWTH AS PER WEEDICIDE STANDARD PRACTICE INCLUDING CLEANING OF ENTIRE AREA, COLLECTION OF DEBRIS AND TRANSPORTING OF CUT GRASS OUTSIDE THE OWNER'S PREMISES &amp; COMPLETE AS DIRECTED., THE ACTIVITY WILL BE DONE ONCE BEFORE START OF MONSOON AND SHALL COMMENCE THE WORK WITHIN 2 DAYS FROM THE INTIMATION NOTICE BY CONCERNED TATA POWER ENGINEER. AFTER REMOVAL OF WILD GROWTH, DURING THE FIRST ONE MONTH PERIOD, VENDOR HAS TO ENSURE THAT THERE IS NO FORMATION OF WILD GROWTH INSIDE THE ENTIRE COMPANY PREMISES AND NO EXTRA PAYMENT WILL BE MADE FOR MAINTAINING THE COMPANY PREMISES AREA DURING THE ONE MONTH PERIOD. IF COMPLAINT OR SAFETY OBSERVATION FOR NON REMOVAL OF GRASS/VEGETATION IS RECEIVED THERE WILL BE PENALTY OF RS. 500 PER COMPLAINT WILL BE CHARGED AND WILL BE DEDUCTED FROM BILL &amp; VENDOR NEED TO ENSURE ZERO GRASS/WILD GROWTH CONDITIONS AND REPORTS.</p>	1	EA
17	REM. GRASS/VEGETA NONOPNL MINOR MONSOON	<p>PROVIDING ALL YOUR TOOLS, TACKLES, EQUIPMENTS AND MINOR SERVICES FOR REGULAR INSPECTION OF AREA FOR ANY VEGETATION GROWTH AND ARRANGE MANPOWER IMMEDIATELY FOR REMOVAL OF VEGETATION AND WILD GROWTH/SHRUBS, IF FOUND BY CUTTING THE ROOTS INSIDE THE NON-OPERATIONAL AREA INCLUDING REMOVAL OF METAL, UPROOTING FROM ROOTS AND RESTORING METAL DISTURBED OR UPROOTING FROM THE GARDEN AREA, INCLUDING INTERNAL CREEPERS ON COMPOUND WALL/FENCING/BARBED WIRE (CREEPERS SHOULD BE REMOVED IMMEDIATELY WHEN IT IS ON GROUND) ETC. WHICH INCLUDED NECESSARY ACTION LIKE WEEDICIDE TREATMENT TO ENSURE NO VEGETATION GROWTH AS PER WEEDICIDE STANDARD PRACTICE INCLUDING CLEANING OF ENTIRE AREA, COLLECTION OF DEBRIS AND TRANSPORTING OF CUT GRASS OUTSIDE THE TATA POWER PREMISES &amp; COMPLETE AS DIRECTED AND SHALL COMMENCE THE WORK WITHIN 2 DAYS FROM THE INTIMATION NOTICE BY CONCERNED TATA POWER ENGINEER. AFTER REMOVAL OF WILD GROWTH, DURING THE ENTIRE ONE MONTH PERIOD, VENDOR HAS TO ENSURE THAT THERE IS NO FORMATION OF WILD GROWTH INSIDE THE ENTIRE OPERATIONAL PREMISES AND NO EXTRA PAYMENT WILL BE MADE FOR MAINTAINING THE COMPANY PREMISES AREA DURING THE ONE MONTH PERIOD. IF COMPLAINT RECEIVED FROM DIVISION THERE WILL BE PENALTY OF RS. 500 PER COMPLAINT WILL CHARGED AND WILL BE DEDUCTED FROM BILL &amp; VENDOR NEED TO ENSURE ZERO GRASS/WILD GROWTH CONDITIONS AND REPORTS. (DURING MONSOON PERIOD)</p>	5	MON

18	REM GRASS/VEGETA NONOPN MINOR NONMONSOON	PROVIDING ALL YOUR TOOLS, TACKLES, EQUIPMENTS AND MINOR SERVICES FOR REGULAR INSPECTION OF AREA FOR ANY VEGETATION GROWTH AND ARRANGE MANPOWER IMMEDIATELY FOR REMOVAL OF VEGETATION AND WILD GROWTH/SHRUBS, IF FOUND BY CUTTING THE ROOTS INSIDE THE NON-OPERATIONAL AREA INCLUDING REMOVAL OF METAL, UPROOTING FROM ROOTS AND RESTORING METAL DISTURBED OR UPROOTING FROM THE GARDEN AREA, INCLUDING INTERNAL CREEPERS ON COMPOUND WALL/FENCING/BARBED WIRE (CREEPERS SHOULD BE REMOVED IMMEDIATELY WHEN IT IS ON GROUND) ETC.WHICH INCLUDED NECESSARY ACTION LIKE WEEDICIDE TREATMENT TO ENSURE NO VEGETATION GROWTH AS PER WEEDICIDE STANDARD PRACTICE INCLUDING CLEANING OF ENTIRE AREA, COLLECTION OF DEBRIS AND TRANSPORTING OF CUT GRASS OUTSIDE THE TATA POWER PREMISES & COMPLETE AS DIRECTED AND SHALL COMMENCE THE WORK WITHIN 2 DAYS FROM THE INTIMATION NOTICE BY CONCERNED TATA POWER ENGINEER. AFTER REMOVAL OF WILD GROWTH,DURING THE ENTIRE ONE MONTH PERIOD, VENDOR HAS TO ENSURE THAT THERE IS NO FORMATION OF WILD GROWTH INSIDE THE ENTIRE OPERATIONAL PREMISES AND NO EXTRA PAYMENT WILL BE MADE FOR MAINTAINING THE COMPANY PREMISES AREA DURING THE ONE MONTH PERIOD. IF COMPLAINT RECEIVED FROM DIVISION THERE WILL BE PENALTY OF RS. 500 PER COMPLAINT WILL CHARGED AND WILL BE DEDUCTED FROM BILL & VENDOR NEED TO ENSURE ZERO GRASS/WILD GROWTH CONDITIONS AND REPORTS. (DURING NON MONSOON PERIOD)	6	MON
19	REMOVAL OF EXTERNAL CREEPERS	PROVIDING SERVICES FOR REMOVAL OF EXTERNAL CREEPERS FROM COMPOUND WALL FENCING,CONCERTINA COIL,BARBED WIRE ETC. INCLUDING TRANSPORTING OF CUT CREEPERS OUTSIDE THE TATA POWER PREMISES ETC. COMPLETE AS DIRECTED. THE ACTIVITY SHALL BE DONE AT INTERMITTENT LOCATIONS THROUGHOUT THE YEAR AND CONTRACTOR SHALL COMMENCE THE WORK WITHIN 2 DAYS FROM THE INTIMATION NOTICE BY CONCERNED TATA POWER ENGINEER .RATE SHALL BE INCLUDING OF ARRANGING SCAFFOLDING & LADDER FOR CARRYING OUT THE WORK., NOTE: 1)THE CREEPERS AVAILABLE IN AN INTERMITTENT LOCATIONS OR IN AN SPOTTED LOCATIONS SHALL BE MEASURED AND PAID FOR., 2) ALL INVOICE COPIES SHALL BE SUPPORTED WITH THE BEFORE AND AFTER PHOTOGRAPH OF WILD GROWTH OPERATION,	2,900	M2
20	CLEANING MOSS WITH OWN BLEACHING POWDER	PROVIDING ALL SERVICES TOOLS, TACKLES, CLEANING MATERIALS ETC. FOR REMOVAL/CLEANING OF MOSS DEPOSITED ON PATHWAYS, CONCRETE SURFACE,TERRACE, ROAD, STEPS ETC BY SCRUBBING, CLEANING, WASHING INCLUDING BLEACHING POWDER/EQUIVALENT CHEMICAL POWDER, WIRE BRUSH ETC. CONTRACTOR SHOULD MAKE HIS OWN ARRANGEMENT FOR STORING BLEACHING POWDER ETC COMPLETE AS DIRECTED BY SITE ENGINEER.	731	M2
21	CLEAN MOSS WITH BLEACHING POWDER BY TATA	PROVIDING ALL SERVICES TOOLS, TACKLES, CLEANING MATERIALS ETC. FOR REMOVAL/CLEANING OF MOSS DEPOSITED ON PATHWAYS, CONCRETE SURFACE,TERRACE, ROAD, STEPS ETC BY SCRUBBING, CLEANING, WASHING INCLUDING, WIRE BRUSH,BROOM ETC. BLEACHING POWDER WILL BE PROVIDED BY TATA POWER	6,525	M2
22	CLEANING OF RAIN WATER GUTTER	PROVIDING ALL YOUR TOOLS, TACKLES, EQUIPMENT, SERVICES ETC. FOR CLEANING OF RAIN WATER GUTTER TO MAKE IT FREE FROM DRY LEAVES OR ANY OTHER CONCRETE/PLASTIC/METAL DEBRIS, AND FLUSHING CONNECTED DOWN TAKE PIPES, PAYMENT TO BE MADE ONLY FOR LENGTH OF DRAIN GUTTER	653	M
23	ONLY SUPPLYING OF TARPAULIN SHEET 200GSM	SUPPLYING ONLY OF TARPAULINE SHEET OF 200 GSM OF ANY SIZE AND SHADE AS DIRECTED BY ENGINEER IN CHARGE. RATE SHALL INCLUDE THE COST OF TRANSPORTATION,LOADING,SHIFTING AND UNLOADING OF MATERIAL AT SITE AND HANDING OVER THE MATERIAL TO PERSON DESIGNATED BY RESPECTIVE DIVISION INCHARGE WITH DOCUMENTATION.THIS ITEM IS EXCLUSIVE OF SPREADING OF TARPAULIN SHEET.	986	M2

24	SPREADING TARPAULIN SHEET SUPPLY BY TATA	PROVIDING SERVICES FOR SPREADING OF TARPAULIN SHEET OF 200GSM AT ANY HEIGHT/SHEET/TERRACE INCLUSIVE OF MAKING TYING ARRANGEMENT USING 12MM POLYPROPYLENE/NYLON ROPE, RATE SHALL BE INCLUSIVE OF MAN, MATERIAL, TRANSPORTATION, LADDER, SCAFFOLD TO COMPLETE THE JOB, PAYMENT WILL BE MADE AGAINST AREA COVERED BY TARPAULIN, NOT THE AREA OF TARPAULIN SHEET USED. TARPAULIN SHEET SUPPLIED BY TATA POWER.	1,900	M2
25	SERV. DURING MONSOON OPERATION & NON-OPN	PROVIDING SERVICES FOR DAILY OR AS & WHEN REQUIRED FOR CLEANING OF ROOF, ROOF GUTTER TO ENSURE THAT NO LEAKAGE OCCUR DUE TO BLOCKAGES IN THE DOWNTAKE PIPE & OVER FLOW OF GUTTER INCLUDING SHIFTING OF DEBRIS, GARBAGE, DRY LEAVES, UNWANTED MATERIAL AVAILABLE ON TERRACE & SLOPPING ROOF TERRACE & STACKING AT LOCATION IDENTIFIED AND TAKING OUT OF COMPANY PREMISES . RATE SHALL INCLUDE THE COST OF SHIFTING & FIXING OF TARPAULIN SHEET WITH THE 12MM POLYPROPYLENE/NYLON ROPE IN OPERATIONAL & NON-OPERATIONAL AREA INCLUDE TERRACES & ON LIVE EQUIPMENTS AT ALL HEIGHTS & REMOVING AFTER THE MONSOON PERIOD WHEREVER REQUIRED INCLUDING INSPECTION OF ALL LOCATIONS DURING THE MONSOON PERIOD .RATE SHALL ALSO INCLUDING ATTENDING SEWAGE & STORM WATER DRAIN CHOCKED AS AND WHEN NECESSARY AND AS DIRECTED BY EIC., NOTE: MINIMUM 2 LABOURS ARE TO BE MADE AVAILABLE DAILY OR AS & WHEN REQUIRED FOR A PERIOD OF 5 MONTHS DURING THE MONSOON PERIOD AND PAYMENT SHALL BE MADE ON PRO-DATA BASIS BASED ON AVAILABILITY OF MANPOWER MENTIONED ABOVE IN THE DIVISION	4	MON
26	REPAIR OF RAIN WATER GUTTER	PROVIDING SERVICES FOR REPAIRING AND REFIXING OF EXISTING OR AVAILABLE RAIN GUTTER OF ANY SIZE RATE INCLUDING P/F CLAMPS/BRACKETS OF REQUIRED SIZE. PAYMENT TO BE MADE ONLY FOR LENGTH OF DRAIN GUTTER OF ANY SIZE	73	M
27	INSPECT OF STORM WATER DRAIN (RCC COVER)	PROVIDING ALL NECESSARY SERVICES INCLUDING TOOLS TACKLES,MANPOWER FOR LIFTING OF ANY SIZES RCC DRAIN COVER FOR INSPECTION OF STORM WATER DRAIN .RATE SHALL INCLUDE THE COST OF SHIFTING AND RE-PLACING OF RCC DRAIN COVER IN IT ORGINAL PLACE AFTER COMPLETION OF INSPECTION AS DIRECTED BY EIC.	36	M2
28	Pump House Cleaning near Canteen	PUMP HOUSE CLEANING: Providing all material and Services for cleaning of monsoon pump house catchment tank of size 6.5 M X 4.5 M X 4 M Deep, including 1. draining out available water 2.Removing and refixing of existing flooring, compliance of all confined space points 3.removing and disposal of Accumulated muck etc. as directed by engineer in charge	1	EA
29	Pump House Cleaning near ST 02	PUMP HOUSE CLEANING: Providing all material and Services for cleaning of monsoon pump house catchment tank of size 5.5 M X 3.5 M X 3.5 M Deep, including 1. draining out available water 2.Removing and refixing of existing flooring, compliance of all confined space points 3.removing and disposal of Accumulated muck etc. as directed by engineer in charge	1	EA
30	Pump House Cleaning Near DT1	PUMP HOUSE CLEANING: Providing all material and Services for cleaning of monsoon pump house catchment tank of size 5.5 M X 5.5 M X 3.5 M Deep, including 1. draining out available water 2.Removing and refixing of existing flooring, compliance of all confined space points 3.removing and disposal of Accumulated muck etc. as directed by engineer in charge	1	EA
31	Providing suction pump/gully sucker	Providing suction pump/gully sucker vehicle having capacity upto 3KL for cleaning of sewage chambers ,sewage pipeline , manhole etc	10	EA

**Note:** The above BOQ is indicative/sample in nature for reference, and the line items may vary depending on site conditions and project location.