The Tata Power Company Limited Invites Tenders through E-Tender Two-Part bidding process from interested bidders (with manufacturing / assembling facilities in India) for the following package required for its Transmission Division: -

Procedure for Participating in Tender

Tender Enquiry No.	Work Description	EMD (Rs.)	Tender Participation Fee (Rs.)	Last date & time for Payment of Tender Participation Fee*
CC27SB041	OLA for Earthpit works at various locations of Transmission Division in Mumbai Metropolitan Region for 2 years.	35,000 /-	2,000/-	15.00 Hrs. Monday, 07th Dec 2026

*** Interested bidder is strongly advised not to wait by above time and purchase the tender immediately to get the link for bid submission. This will enable them to communicate/raise queries against the subject tender in time.**

Procedure for Participating in Tender. Following steps to be done before last date for purchase of tender,

1. Interested bidder to refer to the Section C: "Pre-Qualification Requirement" (PQR).
2. Eligible and Interested Bidder to submit duly signed and stamped letter on Bidder's letterhead indicating,
    a. Tender Enquiry number.
    b. Name of authorized person.
    c. Contact number.
    d. e-mail id.
    e. Details of submission of Tender Participation Fee.
3. Non-Refundable Tender Participation Fee, as indicated in table above, to be submitted in the form of Direct deposit in the following bank account and submit the receipt along with a covering letter clearly indicating the Tender Reference number –

    Beneficiary Name – The Tata Power Co. Ltd.

    Bank Name – HDFC Bank Ltd.

    Branch Name – Fort Branch, Mumbai

    Address – Maneckji Wadia Building, Nanik Motwani Marg, Fort, Mumbai 400023.

    Branch Code – 60

    Bank & Branch Code – 400240015

    Account No – 00600110000763

    Account type – CC

IFSC Code – HDFC0000060

E-mail with necessary attachment of 1 and 2 above to be send to shrushti.bhujbal@tatapower.com & with copy to anubhav.anand@tatapower.com before “Last date and time for Payment of Tender Participation Fee”.

Interested bidders to submit Tender Participation Fee and Authorization Letter before Last date and time as indicated above after which link from Tata Power E-Tender system (Ariba) will be shared for further communication and bid submission.

Please note all future correspondence regarding the tender, bid submission, bid submission date extension, Pre-bid query etc will happen only will be strictly done only with interested bidders who have done the above steps in time with Authorized Person only through Tata Power E-Tender system (Ariba). User manual to guide the bidders to submit the bid through e-Tender system (Ariba) is also enclosed.

No e-mail or verbal correspondence will be responded. All communication will be done strictly with the bidder who have done the above steps (Payment of tender fee and submission of letter with requisite details) to participate in the Tender.

Also, it may be strictly noted that once date of “Last date and time for Payment of Tender Participation Fee” is lapsed no Bidder will be sent link from Tata Power E-Tender System (Ariba). Without this link vendor will not be able to participate in the tender. Any last moment request to participate in tender will not be acknowledged.

Any payment of Tender Participation Fee / EMD by Bidder who have not done the pre-requisite within stipulated timeline will not be refunded.

Also, all future corrigendum’s to the said tender, if any, will be informed on Tender section on website https://www.tatapower.com

Earnest Money Deposit (EMD) is not to be submitted now and is required at a later stage along with tender submission in the form of Bank Guarantee and NEFT.

PQR

To be filled by Tata Power				To be filled by Bidder
Sr No	Parameter	Tata Power Requirement	Documents to be submitted by vendor to ascertain meeting of Pre-Qualification Requirement	Bidder response
1	**2**	**3**	**4**	**5**
1	Work experience	1.Bidder should have minimum 5 years of experience in the Construction & refurbishment of earthpits works **(Attach Certificates / related supporting documents)** 2.Bidder must have successfully executed the works of Earthwork,Soling work,PCC work ,brickwork & plaster work,reinformcement steel ,Structural steel,brazing work etc as per the BOQ 3.Bidder should provide minimum two references of PO for having successfully completed a Civil & fabrication works for earthpit refurbishment works having contract value of upto Rs. 20 lakhs (Indian Rupees twenty lakhs) Bidder should also furnish List of Clients for whom they have done road works during the last five financial as per nature of contract. 4.Bidder / Tenderer should preferably have ISO 9001 / ISO 14001 / ISO 45001 certification or must give an undertaking for its willingness to obtain the same within 2 months of qualification for the work. 5.In case the bidder has a previous association with any of Tata Power Group companies for similar products and services, the performance feedback of the bidder by the Tata Power Group companies shall only be considered for evaluation purpose, irrespective of performance certificates issued by any third organization.	1. Bidder to submit POs/Completion Certificates for supporting the experience criteria. 3. ISO 9001 / ISO 14001 / ISO 45001 certification or undertaking.	
2	Safety	The Bidder will have to go through requirement Tata Power Skilled Development Institute (TPSDI) training for workmen, Certifications etc. 100% workmen shall be L1 & L2 and supervisor should be L3 trained & certified by Tata Power Skill Development Institute (TPSDI).	List of TPSDI trained workmen OR undertaking for completion of training.	
3	Financial	Average annual turnover of the Vendor for last three financial years shall not be less than Rs. 35 lakhs for Civil works.	Profit and Loss Statements, Balance Sheet for the Three (3) preceding financial years duly audited and approved by Authorized Audit Firm / CA.	

The Prequalification Criteria (C.1) published along with the tender is the total & complete pre-qualification requirement for the tender and shall prevail over any other/additional pre-qualification requirement mentioned elsewhere in the tender.

BOQ -OLA for Earthpit works at various locations of Transmission Division in Mumbai Metropolitan Region for 2 years.				
Sr. No.	**Short text**	**Item description**	**1st Year Qty**	**Unit**
1	Supplying Marconite rod 100 mm dia	Supplying 3 m long marconite rod by casting marconite compound around 20 mm dia copper rod, rate shall be inclusive of man, material, tools, transportation and installation at site, rod must be free from visible cracks	600.00	EA
2	Const of earth pit 900 x 900	Providing all tools, material & manpower for constructing of new earth pit incl Providing and laying of fine sand in layer in earthing pit, salt, coal, bentonite in earthing pit in layers & 8mm thickness MS plate above it. Rate shall include the cost of loading, transporting and unloading, shifting of material at the designated place & number painting on earth pit plate with synthetic enamel paint as directed by EIC. Size of earth pit as follows 900mm x 900mm	100.00	EA
3	Const of earth pit 1200 x 1200	Providing all tools, material & manpower for constructing of new earth pit incl Providing and laying of fine sand in layer in earthing pit, salt, coal, bentonite in earthing pit in layers & 8mm thickness MS plate above it. Rate shall include the cost of loading, transporting and unloading, shifting of material at the designated place & number painting on earth pit plate with synthetic enamel paint as directed by EIC. Size of earth pit as follows 1200 mm x 1200mm	100.00	EA
4	Refurbishment of earthpit 900 x 900	Refurbishment of existing earth pit rate shall be including removing of existing earthing rod of any size, sand, coal, bentonite, existing earthing pit cover of mild steel /aluminum chequred plate of any size and thickness. making of new earth pit by prov. & laying of fine sand , salt ,coal ,bentonite in earthing pit in layers & 8 mm thick MS plate above it. incl transport, shifting of material & number painting on earth pit plate with synthetic enamel paint. for 900 mm x 900mm	150.00	EA
5	Refurbishment of earthpit 1200x1200	Refurbishment of existing earth pit rate shall be including removing of existing earthing rod of any size, sand, coal, bentonite, existing earthing pit cover of mild steel /aluminum chequred plate of any size and thickness. making of new earth pit by prov. & laying of fine sand , salt ,coal ,bentonite in earthing pit in layers & 8 mm thick MS plate above it. incl transport, shifting of material & number painting on earth pit plate with synthetic enamel paint. for 1200 mm x 1200mm	150.00	EA
6	Prov.,Laying&Fix, UPVC 50mm	Providing & fixing finolex / astral / prince / supreme make schedule 40 CPVC pipe along with necessary bends, 't', joints with copper threaded ends - 50 mm	1125.00	M
7	Prov. & laying PCC M-15 (site mix)	Supplying, providing and laying in position plain cement concrete M15 grade in levelling course/fill under or around foundations, over soling, column, beam, pedestal, footing. At any depth with 20 mm down graded coarse aggregates including curing, compacting, de-watering wherever necessary, providing shuttering form work wherever required etc. Complete for the following mixes: using site mix / mixer machine	100.00	M3
8	Prvov. & const. Brick masonry 230mm	Providing all material and constructing brick masonry 230mm. Thick and above in cement mortar (1:5) using approved quality class 35 conforming to IS 1077 : 1992 table molded bricks, including scaffolding, curing, raking joints, etc. Complete as per specifications & drawings at all levels & locations	275.00	M3

9	P/A external plaster 20mm	Providing all materials and carrying out sand faced plaster 20 mm thick in two layers (first layer of 14 mm and second layer of 6 mm thickness) with waterproofing compound. Including bands drip molds in cement mortar 1:4 including scaffolding (the rates shall include provision for chicken mesh 230 mm wide at the junction of masonry with RCC)..	1400.00	M2
10	Brazing of Copper Conductor 0.2 mm	Providing all material, tools and tackles, service for brazing of 0.2 copper conductor	1125.00	No
11	Demolishing brick masonry	Providing all necessary tools tackles services etc for demolishing brick masonry of variable thickness with plaster and disposing off the debris to the approved dumping ground of municipal corporation area etc complete as per specifications and as directed by the engineer	275.00	M3
12	Prov./ Supply /Fab structural steel	Providing & fabricating & erecting all types of structural steel, work, welding & gas cutting, drilling of hole, with own welding set, gas cutting set, gas, approved quality of welding electrode, drill machine, required for carrying out work, the rate shall include supply & fixing of mild steel bolt, nut, washer & applying one coat of primer & 2 coats of approved synthetic enamel paint to all the exposed surfaces of steel(excluding chequered plate)	5.00	TON
13	Laying Copper Conductor 0.2mm	laying copper conductor,0.2mm, providing all tools & tackles for laying conductor in line as directed by EIC	1000.00	M
14	Sup/Fab/Placing Reinforcement Steel	Providing & binding reinforcement steel of any dia including binding wires, cleaning, bending, cutting, hoisting, placing in position, lapping and binding with 16 SWG annealed soft iron wire or tack welding reinforcement steel for all types of RCC work irrespective of locations & levels all as per drawings including handling and transporting steel from nearest stores to site complete as directed for HYSD bars.(FE-500 conforming to IS code 1786-1985).	2.00	TON
15	PRVD& SPLY RED SOIL	SUPPLYING AND LAYING OF NATURAL RED SOIL AT SITE IN EARTH PIT AS DIRECTED BY EIC.RATE SHALL INCLUDE LOADING ,TRANSPORTATON AND UNLOADING OF MATERIALS AT SITE.	500.00	M3
16	Prov. Cartage services	Providing cartage service & transporting, excavated soil, debris, bricks, concrete, dry garbage etc.and disposing off to municipal corporation area approved dumping sites outside premises incl submission of relevant documents. Note: measurement will be made on truck measurement.	500.00	M3